

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-21,414-0000

LEASE NAME Wells

WELL NUMBER 1-22

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 22 TWP. 34 SRGE. 36 (X) or (W)

COUNTY Stevens

Date Well Completed 8-14-90

Plugging Commenced 9-24-93

Plugging Completed 10-14-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ensign Operating Co.

ADDRESS 621 17th St., #1800, Denver, CO 80293

PHONE# (303) 293-9999 OPERATORS LICENSE NO. 04782

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-93 (date)

by KCC District Office at Dodge City, Kansas (KCC District Agent's Name),

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6800

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		1787	0	8 5/8	1787	0
		6788	0	4 1/2	6788	3633

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Blew down tbg & csg. TOH & LD tbg string. Capped 4 1/2" Prod csg. Mixed & pmpd 2 sx of CSH & 20 sx cmt. Displ thru 4 1/2" prod csg w/drlg mud to perfs from 6031-6231. Backed off 4 1/2" prod csg at 3663' & POOH.

Circ to spot 50 sx cmt from 3050-3200' w/drlg mud back to 1820'. (OVER)  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ensign Operating Co.

City & Denver STATE OF Colorado COUNTY OF Denver, ss.

Conni Smith

(Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Conni Smith

(Address) 621 17th St., #1800, Denver, CO 80293

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of October, 19 93

Paula R Campbell  
Notary Public

My Commission Expires: 9/30/94

Circ to spot 50 sx cmt from 1670'-1820' w/drlg mud back to 700'.  
Circ to spot 40 sx cmt from 600-700' w/drlg mud back to 40'.  
Circ to spot 10 sx cmt from 40-3'. Cut off & capped surf csg 3' below GL.