


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-191-30039-0000

RP

NORTH



Locate well correctly on above Section Plat

SUMNER County. Sec. 9 Twp. 35S Rge. ~~XXXXXX~~ 2 (W)

Location as "NE/CNW&SW" or footage from lines SW NE NE
Lease Owner REX & MORRIS, ET AL
Lease Name STEPHENS Well No. 1
Office Address P. O. BOX 334, EL DORADO, KANSAS 67042
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 13 AUGUST 19 65
Application for plugging filed 13 AUGUST 19 65
Application for plugging approved 13 AUGUST 19 65
Plugging commenced 13 AUGUST 19 65
Plugging completed 13 AUGUST 19 65
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HOWARD HESS
Producing formation NONE Depth to top _____ Bottom _____ Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	SURFACE	259'RB	8 5/8"OD	253.94'	LEFT IN
(SEE ATTACHED LOG)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY DRILLING MUD TO 275', SET PLUG AND HULLS AND CEMENTED WITH 20 SACKS CEMENT, FILLED HOLE WITH MOD TO 40', PUSHED PLUG TO 40', PUT IN HULLS AND CEMENTED WITH 8 SACKS CEMENT, PUT 2 SACKS CEMENT IN RAT HOLE.

FILED
AUG 10 1965
8-19-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor REX & MORRIS DRILLING COMPANY
Address P. O. BOX 334, EL DORADO, KANSAS 67042

STATE OF KANSAS, COUNTY OF BUTLER, ss.
A. H. FISHER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Fisher
P. O. BOX 334, EL DORADO, KANSAS 67042
(Address)

SUBSCRIBED AND SWORN TO before me this 17TH day of AUGUST, 19 65

My commission expires 5 MAY 1969
Hazel N. Dilts
HAZEL N. DILTS Notary Public.

STEPHENS #1

REX & MORRIS, ETAL

Elevation 1128' RB
1123' DF

Total Depth: 4740' RB
Contractor: Rex & Morris
Commenced: 8-2-65
Completed: 8-13-65
Initial Prod.: D. & A.

Location: SW NE NE
Section 9-358-2W
Sumner County, Kansas
Casing Record:
8 5/8" OD Set at 259' RB W/200 Sacks

FORMATION	DEPTH
Surface Hole	259'
Shale & Lime	698'
Lime & Shale	2200'
Shale & Lime	2692'
Lime & Shale	2820'
Shale & Lime	3249'
Lime & Shale	3400'
Shale & Lime	3465'
Sand	3580'
Lime	3843'
Lime & Shale	3970'
Lime	4032'
Lime & Shale	4279'
Lime	4657'
Shale	4690'
Shale & Lime	4732'
Lime	4740'

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1965
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By *A. H. Fisher*
A. H. Fisher

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 17th day of August, 1965.

Hazel N. Dilts
Hazel N. Dilts, Notary Public

My commission expires: May 5, 1969