

15-191-21582-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY SUMNER SEC. 9 TWP. 35S RGE. 2W E/W
 Location as in quarters or footage from lines:
 NW NE SE

Lease Owner TXO PRODUCTION CORPORATION
 Lease Name WHITE AC #1 Well No. #1
 Office Address 200 W. DOUGLAS, SUITE 300, WICHITA, KS, 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
 Date Well Completed 2:30 P.M. 9-15-83
 Application for plugging filed 9-20-8
 Plugging commenced 1:00 P.M. 9-15-83
 Plugging completed 2:30 P.M. 9-15-83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well WARREN KIRKPATRICK

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	252'	J-55	6 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged WHITE AC #1 with 115 sks 2% gel, 3% cc. 1st plug 1200' 35 sks,
 2nd plug 300' 35 sks, 3rd plug 60' 25 sks, 10 sks rat hole, 10 sks, mouse hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SUN OILWELL CEMENTING

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


(employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Arnie Little ARNIE LITTLE
 VICE-PRESIDENT
 BOX 18611, WICHITA, KS. 67207
 (Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of SEPTEMBER, 19 83

Kathleen G. Quinn
 KATHLEEN G. QUINN
 Notary Public.
 STATE CORPORATION COMMISSION

My Commission expires: MARCH 20TH, 1987



SEP 22 1983

CONSERVATION DIVISION
 Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15-191-21582-0000



WELL LOG

WELL NAME: WHITE AC #1

WELL LOCATION: NW NE SE,

SEC. 9-35S-2W

OPERATOR: TXO PRODUCTION CORPORATION

COMMENCED: 4:15 P.M. 9-3-83

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 2:30 P.M. 9-15-83

CASING RECORD: _____

8 5/8" set @ 252'

FORMATION:

FROM:

TO:

Blue Shale	0'	270'
Red Bed	270'	420'
Shale-Lime	420'	3523'
Sand	3523'	3572'
Kansas City	3572'	3612'
Lime	3612'	4046'
Lime-Shale	4046'	4228'
Lime	4228'	4238'
Lime-Shale	4238'	4290'
Mississippi	4290'	4762'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
NW NE SE, SEC. 9-35S-2W, SUMNER CO., KS. TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.
Arnie Little
ARNIE LITTLE
VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20TH DAY OF SEPTEMBER, 1983

MY APPOINTMENT EXPIRES MARCH 20, 1987
KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Appl. Exp. 3-20-87

RECEIVED
STATE CORPORATION COMMISSION
Kathleen G. Quinn
KATHLEEN G. QUINN
NOTARY PUBLIC

SEP 22 1983