

15-191-20314-0000 R


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sumner County, Sec. 3 Twp. 35S Rge.      (E) 2W (W)  
Location as "NE/CNWSW" or footage from lines C SW SW  
Lease Owner THE NATIONAL OIL COMPANY  
Lease Name Slentz Well No. 1  
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-9 1972  
Application for plugging filed 1-9 1972  
Application for plugging approved 1-9 1972  
Plugging commenced 1-9 1972  
Plugging completed 1-9 1972  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham  
Producing formation      Depth to top      Bottom      Total Depth of Well 4755 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	250'	8-5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Fluid to 240, 1/2 sx hulls, plug, 20 sx cement;  
Fluid to 40, 1/2 sx hulls, plug, 10 sx cement;  
Two sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.  
Address 737 First National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF     , ss.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
737 First Nat'l Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1972

My commission expires August 25, 1972

Ella Priess  
Ella Priess Notary Public.

15-191-20314-0000 R

DRILLERS' LOG

THE NATIONAL OIL COMPANY  
No. 1 Slentz  
C SW SW, Section 3-35S-2W  
Sumner County, Kansas

Elev: 1125 R.B.

Commenced: 12-26-71  
Completed: 1-8-72

Surface Casing: 250' of  
8-5/8" cemented w/200 sx  
cement, 3% cc. 12-26-71.

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	256
Shale	550
Lime & Shale	1167
Shale & Lime	1321
Lime & Shale	1975
Shale & Lime	2212
Lime & Shale	2931
Shale & Lime	3078
Sand	3194
Shale & Lime	3582
Lime	3725
Lime & Shale	3851
Shale & Lime	3887
Lime	4088
Lime & Shale	4260
Cherty Lime	4273
Lime	4518
Lime & Shale	4755 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*

JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state this 12th day of January, 1972.

My Commission Expires:  
August 25, 1972

*Ella Priess*  
Ella Priess, Notary Public

