

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-191-21,979-0000

LEASE NAME F. E. Strickland

WELL NUMBER 1

4541 Ft. from S Section Line

3515 Ft. from E Section Line

SEC. 12 TWP. 35S RGE. 1 ~~KXXXX~~(W)

COUNTY Sumner

Date Well Completed 3-21-87

Plugging Commenced 3-21-87

Plugging Completed 3-21-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McGowan Oil Co.

ADDRESS 302 N. Summit, Arkansas City, KS 67005

PHONE#(316) 442-1413 OPERATORS LICENSE NO. 3231

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? District 2

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation ACO-1 and well log will be filed by Operator.
N/A Depth to Top _____ Bottom _____ T.D. 4248'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill hole with mud. Spotted 20 sx. cement @ 1500'. Spotted 20 sx. cement @ 1400'.
Spotted 35 sx cement @ 310'. Spotted 10 sx cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine

(Address) 401 E. Douglas - Suite 500, Wichita, KS 67202


SUBSCRIBED AND SWORN TO before me this 27th day of March, 1987

David F. Jamis
Notary Public
STATE CORPORATION COMMISSION

My Commission Expires:



MAR 30 1987 Form CP-4
Revised 07-86
CONSERVATION DIVISION
Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: McGowan Oil Co., 302 N. Summitt, Arkansas City, KS 67005

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name F. E. Strickland Well No. 1

Sec. 12 T. 35S R. 1W Spot SW NE NW

County Sumner State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 260' with 175 sx. 3% CC

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4248'

Drilling Commenced 3-10-87 Drilling Completed 3-21-87

Formation	From	To	Tops	
Cellar	0	10	Mississippi	3807
Shale	10	261	Simpson	4191
Shale, Lime	261	445		
Lime, Shale	445	840		
Shale, Lime	840	1818		
Lime	1818	1901		
Sand	1901	1975		
Lime	1975	2265		
Shale, Lime	2265	2515		
Sandy Shale, Lime	2515	2655		
Shale	2655	2699		
Lime	2699	2704		
Shale	2704	2750		
Sand	2750	2942		
Shale	2942	3141		
Sand	3141	3267		
Lime	3267	3482		
Shale	3482	3511		
Lime	3511	3640		
Shale, Lime	3640	3701		
Shale	3701	3807		
Lime	3807	4132		
Shale	4132	4191		
Sand	4191	4248		

STATE CORPORATION COMMISSION
 MAR 30 1987
 CONSERVATION DIVISION
 Wichita, Kansas