

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

SUMNER

County, Sec. 11 Twp. 35 Rge.      (E) 1 (W)

Location as "NE/CNWxSWx" or footage from lines NW NW NW  
Lease Owner E. H. Adair - Lee Phillips  
Lease Name Grow Well No. 1  
Office Address 1017 East Second, Wichita 7, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 13, 1955  
Application for plugging filed February 13, 1955  
Application for plugging approved February 13, 1955  
Plugging commenced February 13, 1955  
Plugging completed February 13, 1955  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production      19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington, Rt 2, Gueda Springs, Ks

Producing formation      Depth to top      Bottom      Total Depth of Well 4231 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	371'	
Copy of Well Log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Placed bottom plug at 330' cemented with 15 sacks, top plug at 30' cemented with 10 sacks, filled to surface.

RECEIVED  
FEB 24 1955  
2-24-55  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor E. H. Adair Oil Company 207  
Address 1017 East Second St., Wichita 7, Ks.

STATE OF Kansas COUNTY OF Sedgwick ss.  
K. W. Johnson (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K W Johnson

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1955

(Address)  
[Signature]

My commission expires September 15th, 1957

Notary Public.

PLUGGING  
MHA REC 11, 35, NW  
BOOK PAGE 97 LINE 21

E. H. ADAIR OIL COMPANY  
WICHITA 7, KANSAS

E. H. Adair Oil Company and  
Lee Phillips

Comm. 1-26-55  
Comp. 2-13-55  
Cont. E.H. Adair  
8 5/8 @ 371' w/ sx

Crow #1  
NW NW NW 11-35-1W.,  
Sumner County, Kansas

Pro. D & A

elev. 1090 KB

figures indicate bottom of formation

Lime and Shale to 1275  
 Shale and Shells 1885  
 Lime and Shale 2316  
 Shale 2605  
 Shale and Lime 2700  
 Shale 2721  
 Lime 2725  
 Shale 2763  
 Sand, Lime 2769  
 Sand 2855  
 Shaley sand 2913  
 Lime 2932  
 Shale 3153  
 Lime 3156  
 Shale 3163  
 sand 3202  
 Shale 3219  
 Sand 3255  
 Shale 3295  
 Sandy Shale 3318  
 Shale 3350  
 Sandy lime 3378  
 Lime 3400  
 Limey Shale 3424  
 Shaley Lime 3464  
 Shaley Sand 3503  
 Shale 3524  
 Lime 3535  
 Shale 3543  
 Shaley Lime 3555  
 Lime 3568  
 Shale 3580  
 Lime 3592  
 Shale 3597  
 Lime 3615  
 Shale, black 3620  
 Lime, Cherty 3651  
 Shale 3653  
 Limey Shale 3670  
 Shale 3733  
 Shale, sandy 3788  
 Shale, limey 3849  
 Shaley lime 3876  
 Chert 3917  
 Cherty lime 3945  
 Chert 3980

Cherty Dolomite to 4154  
 Shale 4204  
 Shale, black 4223  
 Sand 4231  
 T. D. 4231

Geological Tops

Stalmer 2769-1679  
 Layton 3163-2073  
 K.C. Lime 3350-2260  
 Oswego 3524-2434  
 Mississippi 3876-2786  
 Kinderhook 4154-3064  
 Chattanooga 4204-3114  
 Simpson 4223-3133

CERTIFIED CORRECT

*J. W. Johnson*

VED  
COMMISSION

241055

MINING DIVISION  
Kansas

**PLUGGING**  
 FILE SEC 11 T 35 R 1 W  
 BOOK PAGE 92 LINE 21