


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 19 Twp. 34S Rge. 41W (E) (W)

Location as "NE/CNW&SW&" or footage from lines C SW NE
Lease Owner Anadarko Production Company
Lease Name Tucker Well No. 01
Office Address Box 351, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-4 1957
Application for plugging filed 2-10 1965
Application for plugging approved 19
Plugging commenced 3-9 1965
Plugging completed 3-9 1965
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production February 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 5250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1492	
				5-1/2	4785	2708

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 35 sxs. cement at 3000'. Spotted 35 sxs. at 700' and spotted 15 sxs. at 45'.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address 1546 Clay Court, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
V. K. Downey, Supt. Drlg. & Prod. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey
Box 351, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1965

Donald L. Vangieson
Notary Public.
Donald L. Vangieson

My commission expires
My Commission Expires Sept. 29, 1968

DRILLER'S LOG

WELL NAME: Tucker No. 01 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351, Liberal, Kansas

WELL LOCATION: C 1/4 SW 1/4 NE 1/4,
1980 ft. ~~North of South line~~, south of north line
1980 ft. ~~East of West line~~; Sec. 19, Twp. 34S, Rge. 41W, Morton County, Kansas
 west east

DRILLING STARTED 5-12, 1957; DRILLING COMPLETED 6-4, 1957
 WELL COMPLETED 7-1, 1957; WELL CONNECTED _____, 19____

ELEVATION: 3458 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
	4674	4684			
	4397	4408			

STATE OF KANSAS
 CORPORATION COMMISSION
 APR 27 1965
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	1492'	300	
5-1/2"	4780'	500	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface clay & sand	0	165	Shale & lime	2240	3090
Sandy shale & shells	165	300	Lime	3090	3570
Red bed & shells	300	795	Lime & shale	3570	3785
Red bed, gyp & sand	795	1070	Lime	3785	3870
Sandy shale & shells	1070	1370	Lime & shale	3870	4414
Red bed, shale & shells	1370	1410	Shale	4414	4485
Anhydrite	1410	1458	Shale & lime	4485	4741
Shale & shells	1458	1477	Shale	4741	4920
Anhydrite	1477	1500	Lime & shale	4920	5149
Shale & shells	1500	1960	Lime	5149	5250-T.D.
Shale & shells w/sand strks	1960	2060			
Lime & shale	2060	2167			
Shale, sand & lime	2167	2240			

RESULTS of INITIAL PRODUCTION TEST: Swabbed & flowed 10 BOPH.