

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Morton County, Sec. 11 Twp. 34 Rge. 41(W)

Location as "NE/CNW/SW" or footage from lines SW NW SW  
Lease Owner Cities Service Company  
Lease Name Eagley A Well No. 3  
Office Address 3545 N. W. 58th Street, Oklahoma City, Oklahoma 73112  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-2 19 78  
Application for plugging filed 2-2 19 78  
Application for plugging approved 2-7 19 78  
Plugging commenced 2-2 19 78  
Plugging completed 2-2 19 78  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Spotted cement plugs as follows:  
50 sx. 5220-5370' - Morrow, Keyes & Chester  
75 sx. 2250-2460' - Hugoton  
34 sx. 1457-1557' - Base Surface casing  
10 sx. 4'-34' - Top hole  
10 sx. Mouse Hole  
10 sx. Rat Hole

Dut off 8-5/8" casing @ 4' and welded on steel cap with well name and date.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1978  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton  
Address P.O. Drawer 1431, Duncan, Oklahoma 73533

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.  
W. A. Givens (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.A. Givens W.A. Givens  
Engineering Manager

3545 N. W. 58th Street, Oklahoma City, OK 73112  
(Address)

Subscribed and sworn to before me this 13th day of February, 1978



Diana S. Gary  
Diana S. Gary Notary Public.

10-3-81

## FORMATION, TESTING AND COMPLETION RECORD

Show Drill Stem Tests,  
Well Stimulation and  
Production Tests

Formation	Top	Bottom	
Red Bed	0	646	DST #1 (Lansing) 3934-3964
Red Bed & Sand	646	1507	
Red Bed	1507	1694	DST #2 (Topeka) 3180-3230
Red Bed & Anhydrite	1694	2063	
Red Bed & Shale	2063	2363	
Shale	2363	2510	Logging: Dual Induction Laterolog, Compensated
Shale & Lime	2510	2750	Formation Density w/Gamma Ray & Caliper, Compensated
Lime & Shale	2750	4583	Neutron Log from 1503-5447'
Lime	4583	4624	
Lime & Shale	4624	5465	
Total Depth		5465	

RECEIVED  
STATE CORPORATION COMMISSION

MAR 16 1978

CONSERVATION DIVISION  
Wichita, Kansas