

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
330 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20.367-0001

LEASE NAME CHEROKEE "C"

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 34S RGE 41 (E) or (W)

COUNTY MORTON

Date Well Completed 10/02/78

Plugging Commenced 7/14/95

Plugging Completed 7/19/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/14/95 (date)

by MR. GLENN BARLOW (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW Depth to Top 5138' Bottom 5150' T.D. 5500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	OIL	5138'	5150'	8-5/8"	1418'	3'
				4-1/2"	5499'	3014'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pmpd 20 sx cmt + 25 sx hulls from 5138'-4938'. Pull free pt. & shot 4-1/2 csg @ 3218'. Could not work pipe free. Shot 4-1/2" casing @ 3014. Pull pipe free. Pmpd 25 sx cmt. from 3000'-2900'. Pull 4-1/2 csg. to 1450'. Pmpd 50 sx cmt from 1450'-1300'. Pull 4-1/2" casing to 650'. Pmpd 40 sx cmt from 650'-550'. Pull 4-1/2" csg. to 40'. Pmpd 10 sx cmt from 40'-0'. Rec 76 its 4-1/2" csg. Cut off & cap 8-5/8" surf. csg. 3' below ground level. KCC witness: Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

John M. Dolan, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John M. Dolan

(Address) John M. Dolan, Sr. Technical Assistant
P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1995

Freda L. Hinz
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
AUG 6 3 1995
CONSERVATION DIVISION
WICHITA KANSAS