


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Morton County, Sec. 24 Twp. 33 Rge. 41 (E) (W)
Location as "NE/CNW/SW" or footage from lines 1910' N E S and 2313' W E E Lines
Lease Owner Panhandle Eastern Pipe Line Company
Lease Name Barker Well No. 1-24
Office Address P. O. Box 828, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed June 25 1956
Application for plugging filed November 23 1966
Application for plugging approved November 28 1966
Plugging commenced December 1966
Plugging completed December 22 1966
Reason for abandonment of well or producing formation Poor casing and hole
conditions. This well was replaced by the Barker No. 2-24
If a producing well is abandoned, date of last production September 9, 1966
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation Hugoton Depth to top 2174 Bottom 2260 Total Depth of Well 2340 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Krider	Gas	2174	2236	7"	452	None
Winfield	Gas	2236	2298	4 1/2"	2301	613
Upper Ft. Riley	Dry	2298	2340			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

30 sacks cement from Total Depth to 1854'. Filled with mud to 500'.
Cemented from 500' to 400' with 30 sacks. Filled with mud to 50'.
Cemented with 10 sacks from 50' to 10'. Filled with mud and cut-off.
7" surface casing 5' below ground level.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Service
Address 1546 Clay Court, Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Seward, ss.
Ronald L. Cook (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ronald L. Cook
Ronald L. Cook, Production Engineer
P. O. Box 828, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1966

My commission expires September 13, 1970

Joan Taylor
JOAN TAYLOR Notary Public.