

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Morton SEC. 32 TWP. 33 RGE. 41 E/W
Location as in quarters or footage from lines:
C NE

Lease Owner Pan Eastern Exploration Company
Lease Name Ryman Well No. 1-32
Office Address 1701 N. Kansas Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 1-15-58
Application for plugging filed 3-1-84
Plugging commenced 4-27-84
Plugging completed 4-30-84
Reason for abandonment of well or producing formation Gas depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Topeka Depth to top 3069 bottom 3083 T.D. 5472

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Fresh water	40	359	8 5/8	1421	none
Topeka	Gas	3036	3333	4 1/2	3697	1624

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 25 sks. of cement @ 3083 to 2850
Pump 50 sks. of cement @ 1470 to 1370
Pump 30 sks. of cement @ 800 to 700
Put 10 sks. of cement @ 40 to 0
Cut off & cap 8 5/8 3' below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.
(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Joe Kraft
Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 84
My Commission expires: July 23, 1986
Sandra C. Sosa Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1984

CONSERVATION DIVISION
Wichita, Kansas



DRILLER'S LOG

WELL NAME: WYMAN #1-32

WELL LOCATION: 350 ft. W of W line,

and 350 ft. N of W line, (10 10) Sec. 12, Twp. 13, Rge. 11,

Horton County, Kansas. Elevation: 3359 ft. G.L.

COMPANY: Panhandle Eastern Pipe Line Company, Box #979, Liberal, Kansas

CONTRACTOR: Magnum Petroleum Corporation, 801 Union Center Building, Wichita, Kansas

DRILLING COMMENCED: 12/12/57

PRODUCTION INFORMATION:

DRILLING COMPLETED: 1/15/58

Completion Test - 2022 MCF.

WELL COMPLETED:

SOURCE OF DATA: Driller's Reports

WELL CONNECTED:

ROTARY LOG

Description of Formation	Top	Bottom
Top Soil	0	10
Red Bed	10	359
Red Bed & Shale	359	630
Red Bed & Lime Shells	630	1010
Sand & Shale	1010	1355
Shale & Lime	1355	1431
Shale	1431	1475
Red Bed	1475	1508
Shale	1508	2008
Lime & Shale	2008	2985
Lime	2985	3100
Lime & Shale	3100	3277
Lime	3277	3390
Lime & Shale	3390	3451
Lime	3451	3715
Lime & Shale	3715	3790
Lime	3790	3983
Lime & Shale	3983	4075
Lime	4075	4394
Lime & Shale	4394	5080
Shale	5080	5112
Lime & Shale	5112	5340
Lime	5340	5472 70

FORMATIONS

FORMATIONS	Tops
Kridger	2087-2116
Wahawnee	2800-3026
*Topoka	3034-3333
Greenwood Lansing	3333-3608
Lansing	3608
Cherokee	4330
Harrow Shale	4774-5280
Harrow "A" Sand	5120-27
Harrow "B" Sand	5198-5204
Harrow "Keyes" Sand	
	5257-85
Mississippian	5288

*Producing Formation(s)

PERFORATIONS:

- 3631-36 w/4 sh/ft
- 3616-24 w/4 sh/ft
- 3029-73 w/4 sh/ft

WELL TREATMENT RECORD:

- 1/500 gals 15% 1/10/58
- 1/500 gals 15% 1/10/58
- 1/2000 gals 7 1/2% 40 balls & 1000 gals 15% acid 1/11/58