

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-00333-0000

LEASE NAME BAKER

WELL NUMBER 1-33

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 33 TWP. 33S RGE 41 ( E ) or ( W )

COUNTY MORTON

Date Well Completed FEB 1957

Plugging Commenced 11-1-98

Plugging Completed 11-3-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-98 (date)

by STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2074 Bottom 2149 T.D. 2260

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2074	2149	8-5/8"	645	0
				4-1/2"	2253	714

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. PMP 3 SXS HULLS & 20 SXS CMT @ 2074-1874. SHOT 4-1/2" CSG @ 918. 714 OF CSG CAME LOOSE. PULL TO 670. CIRCULATE HOLE W/ 9 PPG MUD. SPOT 50 SXS CMT @ 520-670. TOH WITH REMAINING CSG. LOAD HOW W/ 9PPG MUD. SPOT CMT PLUG @ 40-4'. CUT OFF AND CAP CSG 4' BELOW GL. STATE WITNESS STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC License No. 31151 12-4-98

Address RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young  
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 1998.

Shirley Childers  
Notary Public

My Commission Expires: \_\_\_\_\_

