

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH

		X	

Locate well correctly on above  
Section Plat

Morton County. Sec. 35 Twp. 33 Rge. 41 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C/NW/NW/SE  
Lease Owner Panhandle Eastern Pipe Line Company  
Lease Name Eagley Well No. 1-35  
Office Address Box #979, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 27, 19 56  
Application for plugging filed October 31, 19 56  
Application for plugging approved November 6, 19 56  
Plugging commenced May 21, 19 57  
Plugging completed May 22, 19 57  
Reason for abandonment of well or producing formation Could not recover tools lost in hole, and new well was drilled.  
If a producing well is abandoned, date of last production -- 19 --  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas  
Producing formation -- -- Depth to top -- -- Bottom -- -- Total Depth of Well 2345 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Krider	--	2202		7"	439'	none
Winfield	--	2268		4 1/2"	2320'	903'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to -- feet for each plug set.

Placed cement plug on bottom with 100 sacks common cement, hole filled to 1940 ft. Filled with heavy mud, cemented through pipe at 1183' with 200 sx cement. Filled hole with mud and shot off and pulled 903 ft of 4 1/2" casing. Filled to 450 ft with mud. Placed cement plug from 450 ft to 425 ft with 20 sacks cement. Filled with mud to 30 ft. Placed cement plug from 30 ft to 5 ft with 10 sx cement. Placed steel cap on top of this plug and cemented over. Filled hole to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Well Service  
Address Borger, Texas

STATE OF Kansas, COUNTY OF Seward, ss.  
S. H. Neithercoat (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S H Neithercoat

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June 19 57  
Carl L. Holland

My commission expires November 14, 1957

Notary Public.

PLUGGING  
FILE SEC 35 T 33 R 41W  
BOOK PAGE 113 LINE 35

JUN 25 1957  
CONSERVATION DIVISION  
Wichita, Kansas

## DRILLER'S LOG

WELL NAME: Eagley #1-35  
 WELL LOCATION: NW NW SE of Section 35, Township 33S, Range 41W,  
 COUNTY: Morton STATE: Kansas ELEVATION: 3363'  
 COMPANY: Panhandle Eastern Pipe Line Company  
 CONTRACTOR: Garvey Drilling Company  
 DRILLING COMMENCED: May 25, 1956 OPEN FLOW:  
 DRILLING COMPLETED: May 31, 1956  
 WELL COMPLETED: July 27, 1956 OPEN FLOW, After Acid:  
 WELL CONNECTED: Not Connected Rock Pressure:  
 SOURCE OF DATA: Driller's Report

## ROTARY LOG

Description of Formation	Top	Bottom
Surface Soil & Sand	0'	439'
(Set 7" Surface Casing @ 439' w/100 sacks cement)		
Sandy Red Bed	439'	545'
Red Bed & Sand Streaks	545'	1320'
Red Bed & Shells	1320'	1900'
Red Bed & Lime	1900'	2050'
Red Bed & Shells	2050'	2205'
Red Bed & Lime	2205'	2345' TD
(Set 4½" Production Casing @ 2320' w/300 sacks cement)		

Remarks: Lost perforating tools in hole. Could not recover tools. Abandoned well.

FORMATIONS	Tops	PERFORATIONS
Krider	2202'	None
Winfield	2268'	

## WELL TREATMENT RECORD

This well was not treated.

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV-6-56  
 CONSERVATION DIVISION  
 Wichita, Kansas

## PLUGGING

FILE SEC. 35 T. 33 R. 41W  
 BOOK PAGE 113 LINE 35