

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

0000

API NUMBER 15-129-21225 -

LEASE NAME USA "AC"

WELL NUMBER 2

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 33S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 9-28-93

Plugging Commenced 9-27-93

Plugging Completed 9-28-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-27-93 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation None Depth to Top - Bottom - T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	686	0
				8 5/8	1580	0

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 28 1993
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/drill pipe to 3100', spot 100 sxs 60/40 Class "H", 6% gel cmt plug. 50 sxs at 1650', 50 sxs at 750', 10 sxs 0-40', 15 sxs in rathole, 10 sxs in mousehole. Cut off 8-5/8" csg off 4' below ground level. Weld on cap. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gabbert-Jones, Inc. License No. 5842

Address 333 E. English, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
(Address) Beverly J. Williams, Tech. Asst.
P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1993

Cheryl Steers
Notary Public

My Commission Expires:

