

15-129-00057-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Morton County. Sec. 15 Twp. 33S Rge. 40W (E)____(W)

Location as "NE/CNW%SW%" or footage from lines C NE SW

Lease Owner Panhandle Eastern / Sierra Petroleum - Contr.

Lease Name HAYWARD # Well No. 2 - 15

Office Address Liberal, Kansas / 208 Petr Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 12/30/57 19

Application for plugging filed 12/29/57 19

Application for plugging approved 12/29/57 19

Plugging commenced 12/30/57 19

Plugging completed 12/30/57 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5855 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1614'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mudr from 5855 up to 3000'. Spotted 25 sks cement through drill pipe by Halliburton. Filled hole with heavy mud up to 2000 feet spotted 25 sacks cement through drill pipe by Halliburton. Filled hole with heavy mud up to 1625. Spotted 25 sacks cement through drill pipe by Halliburton. Filled hole up to 600'. Spotted 25 sacks cement through drill pipe by Halliburton. Filled hole to 45 feet and spotted 10 sacks cement through drill pipe by Halliburton. Job complete 7 a.m.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 58

Margie Cooper
Notary Public.

My commission expires 1-30-61.

PLUGGING
FILE SEC 15 T.33 R.404
BOOK PAGE 73 LINE 27

Panhandle Eastern Pipeline Co - Owner

Sierra Petroleum Co., Inc. - Contr

HAYWARD #2 - 15

C NE SW Sec. 15-33S-40W
Morton County, Kansas

Total Depth: 5855

Elev: 3297 GL

Comm: 11/28/57

Comp: 12/30/57

Casing:

Cement:

8 5/8" @ 1614'

with 800 sacks cement

FORMATION	DEPTH
Sand & clay	290
Red bed	640
Sandy gyp	680
Red bed & shale	750
Red bed	820
Shale & lime	1135
Shale & shells	1540
Lime & shale	1600
Anhydrite	1620
Shale & lime	1780
Shale	2065
Shale & sanydrite & shells	2160
Shale & lime	3170
Lime	3210
Lime & shale	3493
Lime	3530
Lime & chert	3540
Lime & shale	3600
Lime	3649
Shale	3695
Lime	3718
Lime & chert	3768
Lime	3836
Lime & shale	3945
Lime	3988
Lime & shale	4074
Lime	4146
Lime & shale	4742
Lime	4790
Lime & shale	4824
Lime	4878
Shale & lime	5166
Shale	5210
Shale & lime	5287
Shale	5407
Sand & lime	5413
Shale	5445
Shale w/sand	5552
Sand	5572
Shale & sand	5607
Shale & lime	5616
Shale & sand	5623
Lime & shale	5690
Shale	5745
Lime	5785
Shale & lime	5816
Lime	5855

Tops:	Anhydrite	1600
	Lansing K. C.	3882
	Keys Sand	5652
	Mississippi	5745

PLUGGING
 FILE SEC 15 T 33 R 406
 BOOK PAGE 73 LINE 27

RECEIVED
 STATE CONSERVATION COMMISSION
 JAN 3 1958
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)
 COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and correct to the best of my knowledge.
 Subscribed and sworn to before me this C. P. Hansker
 2nd day of January, 1958.
 My comm expires: 1-30-61.
Margie Cooper
 Notary Public