

15-129-20074-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 3-21-72 Drill Date

LEASE NAME Low "C"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4

3300 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 17 TWP. 33 SRGE. 40 (E or W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 3-31-72

Character of Well Oil

Plugging Commenced 1-7-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-12-93

The plugging proposal was approved on 1-2-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation St. Louis/Morrow Depth to Top 5460 Bottom 5692 T.D. 5753

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8	120	0
				8 5/8	1495	0
				5 1/2	5753	2216

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/4 tbg to 5388. Pmpd 2 sxs hulls + 25 sxs cmt plug @ 5188-5388. TOH w/tbg to 5100' Circ w/mud. Shot 5 1/2 csg @ 2216. Rec 68 jts 5 1/2 csg. TIH w/1 1/4 tbg to 2000. Pmpd 30 sxs cmt from 2200-2100, 50 sxs cmt from 1530-1430, 35 sxs cmt from 700-600, 10 sxs from 40-3'. Cut off csg & capped 8 5/8 csg 3' below ground level. KCC witnessed - Glenn Barlow. Restore
(If additional description is necessary, use BACK of this form.) location.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Eng. Tech. P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1993

Cheryl Steers
Notary Public

My Commission Expires: _____



RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 1993
CONSERVATION DIVISION
WICHITA, KS