

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20530-0002

LEASE NAME LOW

WELL NUMBER D-6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

1650 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 33 RGE 40 (E) or (W)

COUNTY MORTON

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 8-1-1981

Plugging Commenced 6-12-2002

Plugging Completed 6-14-2002

The plugging proposal was approved on 6-1-2002 (date)

by JIM HOLLAND (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation WABAUNSEE Depth to Top 2914 Bottom 2961 T.D. 5825

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
WABAUNSEE	GAS	2914	2961	8 5/8	1485	0
				5 1/2	5825	2004

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PMP 3 SXS HULLS & 25 SXS CMT FROM 2914-2714. SHOOT OFF 5 1/2 CSG AT 2004. PULL TO 1515 AND PLUMP 50 SXS CMT FROM 1515 TO 1365. PULL TO 600 AND PMP 40 SXS CMT FROM 550 TO 430. PULL TO 40 AND PMP 10 SXS CMT TO PLUG 40-SURFACE. CUT OFF AND CAP 8 5/8 CSG 3 FEET BELOW GI.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters

CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 9 day of July, 2002

Lori Pearson
Notary Public

My Commission Expires 2/26/05

OR