

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-20075-0000

API NUMBER Not Issued

LEASE NAME Low "D"

WELL NUMBER 4

660 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 18 TWP. 33S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 3/23/72

Plugging Commenced 10/24/89

Plugging Completed 10/24/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Matagorda Island Exploration Corporation

ADDRESS P. O. Box 351, Liberal, KS 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 3316

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 20, 1989 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No (On File with KCC)

Producing Formation St. Louis Depth to Top 5684 Bottom 5690 T.O. 6650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
St. Louis	Oil, Gas, Water	5684	90	4 1/2	5759	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1.) Displaced hole w/70 bbls drilling mud via 2 3/8" tubing. 2.) Spotted 30 sxs 60/40 POZ + 6% Gel + 2% CaCl2 from 5648'-5250'. 3.) Perforated tubing @ 1528' and spotted 25 sxs 60/40 POZ + 2% CaCl2 + 6% Gel from 1528'-1200'. 4.) Shot off tubing @ 712' and spotted 20 sxs 60/40 POZ + 6% Gel from 712'-450'. 5.) Spotted 15 sxs 60/40 POZ + 6% Gel from 50'-3'. (OVER)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Company License No. NA

Address Highway 54W, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Matagorda Island Exploration Corporation

STATE OF Kansas COUNTY OF Seward, ss. NOV 21 1989

M. L. Pease (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease  
M. L. Pease - Division Production Mgr.  
(Address) P. O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1989

CHERYL STEERS  
Notary Public - State of Kansas  
My Comm. Expires 6-1-93

My Commission Expires:

Cheryl Steers  
Notary Public

- 6.) Hooked up to braden head and pumped 200 sxs 60/40 POZ + 6% Gel from 0'-1478'.
- 7.) Cut off wellhead 3' below ground level and welded on cap.
- 8.) Restore location as per Forest Service requirements.

