

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1964

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Fred Wallace of Ambassador Oil Corporation has this date requested permission to plug the following described well:

Mr. Wallace guarantees payment of the plugging fee.

Operator's full Name: Ambassador Oil Corporation

Complete Address: 304 Hightower Bldg., Oklahoma City, Oklahoma

Lease Name: Myer Well No. # 1

Location: SE SW NE Sec. 23 Twp. 32 Rge. 30 (E) (W) W

County Mead Total Depth 6200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wallace was instructed to plug the well as follows:

1617' of 8 5/8" surface pipe, cement circulated with 850
sacks. Push 1st cementing plug to 700', and cement with 35
sacks, through the drill pipe. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat and mou-
se hole with 5 sacks.

Very truly yours,

Archie Elving