

15-119-10218-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Re WELL PLUGGING RECORD

Meade County, Sec. 20 Twp. 32S Rge. 30W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Thomas & Brewer Oil & Gas
Lease Name Bender Well No. # 1
Office Address Box 985 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes 19____
Application for plugging approved yes 19____
Plugging commenced 3-10-60 19____
Plugging completed 3-17-60 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lao Kamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 562 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,318'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 3-10-60. Plugging completed 3-17-60. Measured into total depth 562 1/2'. Bailed down 75' of sand. Dumped 5 sacks of cement. Worked and shot pipe. Shot 5 1/2" casing at 3,318'. Pulled and laid down casing. Plugged well. Mudded to 550'. Set 10' rock bridge at 550'. Dumped 20 sacks of cement. Mudded hole to 40'. Set 10' rock bridge and capped the well with 10 sacks of cement.

STATE CORPORATION COMMISSION
MAR 31 1960
3-31-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
J. O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1960

My commission expires December 8th, 1963. Kayann Jenkins Notary Public.

THOMAS & DREWES
BENDER #1

SE NW SE Sec. 20-32-30
Meade County, Kansas

RTD 5700'

CONTRACTOR: Bennett & Roberts Drilling Co.

Commenced 1/8/60
Completed 1/30/60

Set 8 5/8" casing @ 1607' w/700 sx cnt.
Set 3 1/2" casing @ 5623.79' w/125 sx.

Surface soil & clay	225
Sand	540
Red Bed & Sand Streaks	850
Red Bed, Sand	950
Shale, Red Bed, Shells	1100
Sand	1380
Shale, Sandy Streaks	1595
Anhydrite	1609
Red Bed & Anhydrite	1740
Red Bed & Shale	1845
Salt & Shale	1905
Shale, Shells & Anhy. Stks	2000
Shale & Shells	2560
Shale & Lime	3283
Chalky Lime & Shale	3480
Lime w/chalk streaks	3550
Lime & Shale	3761
Lime	3927
Lime & Shale	4010
Lime	4148
Lime & Shale	4238
Lime	4404
Lime & Shale	4460
Lime	4579
Lime & Shale	4667
Lime	5331
Lime & Shale	5387
Lime	5488
Lime & Shale	5540
Lime	5700

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By Juanice Lee Marshall

Subscribed and sworn to before me this 4th day of February, 1960.

Clara Hummel
Notary Public

My Commission Expires 6/17/62