

15-119-00141-0001

RECEIVED
STATE CORPORATION COMMISSION


MAR 13 1975
3-13-75
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Meade County, Sec. 21 Twp. 32S Rge. (E) 30 (W)
Location as "NE/CNW&SW" or footage from lines
Lease Owner Texas Energies, Inc.
Lease Name Collingwood Well No. 1
Office Address 306 Bank of the S. W. Bldg., Amarillo, Texas 79109
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 3-63 19
Application for plugging filed 2-75 19
Application for plugging approved 2-19-75 19
Plugging commenced 2-21 1975
Plugging completed 2-25 1975
Reason for abandonment of well or producing formation
No Longer Producing
If a producing well is abandoned, date of last production XXXXXX 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Morrow-Mississippian Depth to top 5,547 Bottom 5,604 Total Depth of Well 5647
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow		Surface	5,647	5 1/2	5,645	2820
		Surface	1,650	85/8		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 20 sks. of cement & 2 sks. of hulls from 5778 to 5450
Pump 60 sks. of cement from 1000 to 900
Put 15 sks. of cement from 45 to 0

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter
L. E. Geoffroy (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
306 Bank of the Southwest Bldg., Amarillo, Tex.
(Address)

Subscribed and sworn to before me this 11 day of March, 1975

My commission expires June 1, 1975 [Signature] Notary Public.

15-119-00141-0001


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- JOE N. CHAMPLIN
Farm- Collingwood No. 1

SEC. 21 T. 32 R. 30W
C NW SE

Total Depth. 5773'
Comm. 4-30-58 Comp. 6-1-58
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 6-27-59

County Meade
KANSAS


CASING:

8 5/8" 1650'
5 1/2" 5647'

Elevation. 2766' RB
Production. 10,000,000 CFG

Figures Indicate Bottom of Formations.

surface clay & sand	100
sand and shells	162
sand and gravel	471
red bed-gyp shells	670
Anhydrite	715
red bed and sand	1000
red bed and shale	1065
red bed, gyp shells	
shale	1350
red bed, sand & shells	1565
Anhydrite	1650
sand and red bed	1760
sand and red bed	2085
Anhydrite & lime	2314
shale & shells	2520
shale and lime	2554
lime	2683
shale and shells	2783
lime and shale	2910
red bed & lime strks	3000
shale and lime	3080
sand lime	3148
lime and sand	3158
lime and sandy lime	3280
lime	3342
lime & shells H.	3360
chalk lime	3413
chalky lime	3515
lime & chalk	3573
lime	3854
lime & shale	4001
lime	4080
lime & chalk	4143
lime & shale	4525
lime K.C.	4572
lime	4694
lime & shale	4775
lime	4901
lime & shale	5035
lime	5247
lime & shale	5260
lime	5363
lime & shale	5463
lime	5529
shale & lime	5647
no record	5778
Total Depth	

TOPS: SCOUT	
Herington	2638
Heebner	4235
Toronto	4277
Lansing	4377
Marmaton	5018
Cherokee	5186
Morrow	5494
Morrow Sand	5510
Chester	5574
St. Gen.	5732

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1975
CONSERVATION DIVISION
Wichita, Kansas