

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20,856-0000

LEASE NAME Fox "H"

WELL NUMBER 1

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 32S RGE. 30 KKXor(W)

COUNTY Meade

Date Well Completed 8-3-92

Plugging Commenced 8-3-92

Plugging Completed 8-3-92

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on verbal 8-3-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation None Depth to Top - Bottom - T.D. 6100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1650	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set. Spot 50 sxs cmt plug @ 1660, 50 sxs @ 500, 10 sxs @ 0-40, 15 sxs in rathole, 10 sxs in mousehole. Heavy drlg mud pmpd between each plug. Cmt used 60/40 Pozmix, 6% total gel. Cut off 8 5/8 csg & weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Norseman Drilling, Inc. License No. 03779

Address 200 E. First Street, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward

Beverly J. Williams, Engineering Technician (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 92

Cheeryl Steers  
Notary Public

My Commission Expires: \_\_\_\_\_

