


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Sedgwick County. Sec. 22 Twp. 29 Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines. SE SW SW
Lease Owner E.H. Adair Oil Co., Lee Phillips, et al,
Lease Name Chambers Well No. 1
Office Address 1017 East Second St. Wichita 7, Ks. (Adair)
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/2 1955
Application for plugging filed 9/2 1955
Application for plugging approved 9/2 1955
Plugging commenced 9/2 1955
Plugging completed 9/2 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production. --- 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well S.S. Greider, State Corp. Commission, Wichita

Producing formation --- Depth to top --- Bottom --- Total Depth of Well --- Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Driller's Log attached hereto)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Placed bottom plug @ 330 feet with 15 sacks of cement.
Placed top plug @ 30 feet with 10 sacks of cement.
Filled to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1955 9412-55

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Company
Address Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

K. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


K. W. Johnson

1017 E. Second St., Wichita,
Kansas

SUBSCRIBED AND SWORN TO before me this 15 day of September, 19 55

L. Hill
Notary Public.

My commission expires 9-15-57.



E. H. ADAIR OIL COMPANY
WICHITA 7, KANSAS.

E. H. Adair Oil Company, et al
Chambers No. 1
Sec. 22-29-2W.
SE SW SW of
Sedgwick County, Kansas
El. 1285 K.B.

Comm. 8-19-55
Comp. 9- 2-55
Contractor:
Rig No. 1.
8-5/8 @ 337' w/235 sx.

D. & A.

Figures indicate the bottoms of Formations

8-5/8 @	337	Shale	3226
Lime & shale	1757	Lime	3232
Shale & shells	2380	Limey shale	3240
Lime	2410	Lime	3248
Shale	2422	Shaley lime	3260
Lime	2426	Lime	3264
Shale	2429	Black shale	3267
Black shale	2431	Lime	3286
Shale	2521	Shale	3316
Lime	2524	Lime	3321
Shale	2533	Black shale	3324
Sandy shale	2638	Limey shale	3367
Lime	2640	Black shale	3370
Shale	2643	Lime	3382
Sand	2654	Shaley lime	3398
Sandy shale	2700	Black shale	3402
Shale	2725	Lime	3421
Lime	2726	Black shale	3424
Shale	2733	Shaley lime	3444
Sand	2774	Lime	3448
Shale	2958	Black shale	3450
Lime	2963	Colored shale	3462
Porous Lime	2969	Black shale	3464
Shale	2971	Colored shale	3492
Lime	2975	Black shale	3494
Porous Lime	3000	Shale	3509
Lime	3017	Black shale	3519
Porous Lime	3023	Lime	3522
Lime	3026	Black shale	3525
Porous Lime	3038	Colored shale	3557
Lime	3042	Chert	3578
Oolitic Lime	3052	Lime	3585
Lime	3066	Porous Lime	3589
Black shale	3070	Lime	3602
Lime	3075	Porous Lime	3609
Oolitic lime	3084	Lime	3738
Lime	3100	Cherty lime	3822
Black shale	3101	Lime	3899
Lime	3109	Shale	3907
Black shale	3111	Lime	3913
Oolitic lime	3120	Shale	3919
Lime	3130	Lime	3926
Shale & lime	3141	Dark shale & lime	3988
Dark shale	3144	Sand	3990
Lime	3161	Dolomite	4003
		Sand	4019
		T.D.	4019

DST No. 1 3580-90. Open
1 hour. Shut in 20 min.
Weak blow for 6 min.
Rec. 5 feet rotary mud.

PLUGGING
FLY SEC 22-29-2W
BOOK PAGE 146 LINE 44

Formation Tops

(See next page)

E. H. Adair Oil Co., Lee Phillips Oil Co., et al.
Chambers No. 1

-2-

Formation Tops

Lansing	2725	(1435)
Stalnaker	2733	(1443)
K.C.	2958	(1673)
Base K.C.	3161	(1876)
Miss. Chert	3567	(2282)
Miss. Lime	3578	(2293)
Kinderhook	3927	(2640)
Misener	3988	(2703)
Simpson Dolo.	3990	(2705)
Simpson Sand	4003	(2718)
T.D.	4019.	

Certified Correct::

K. W. Johnson
K.W. Johnson - Geologist

SEP 12 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
PER SEC	I R
BOOK PAGE	LINE