

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sedgwick SEC. 22 TWP. 29S RGE. 2W E/W
Location as in quarters or footage from lines:
C NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Lauer Well No. #1
Office Address 435 Page Court 220 W. Douglas Wichita, Ks, 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 9-4-81
Plugging completed 9-23-81
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett
Producing formation Depth to top bottom T.D. 3985'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	483'	none
				4-1/2"	3678'	3026'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

~~Moved in on location, made bottom plug back with sand to 3600' and set 4 sacks
cement, had 26" stretch. Shot pipe @3135' and 3600', pulled a total of 68 joints.
Plugged well with 3 sacks hulis, 6 sacks gel, 8-5/8" plug and 170 sacks common cement.
Plugging completed.~~

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 1981

My Commission expires:



Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1981

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: Euwer Petroleum Co.

SEC. 22 T. 29S R. 2W

WELL NAME: Lauer #1

LOC. C NE NW

COUNTY: Sedgwick

RIG NO. #3

TOTAL DEPTH 3985'

ELEVATION

COMMENCED: 4-7-80

COMPLETED: 4-20-80

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 483' w/200 sx. common, 3% cc., 2% gel. and 50 sx. common.

PRODUCTION: 4 1/2" @ 3678' w/125 sx. 60/40 poz., 12% salt.

LOG

(Figures Indicate Bottom of Formations)

Shale	2656
Shale & Lime	3063
Shale	3176
Lime	3550
Shale & Lime	3745
Lime	3985
<u>ROTARY TOTAL DEPTH</u>	<u>3985</u>

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Lauer #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 22 day of April, 1980.

Juanita M. Green
Juanita M. Green



My Appointment Expires:

10-4-83