

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-173-19093-0001

API NUMBER

LEASE NAME Struthers

WELL NUMBER #1 SWD

SPOT LOCATION NENE SW

SEC. 2 TWP. 29 RGE. 2 (E) or (W)

COUNTY Sedgwick

Date Well Completed 2-24-57

Plugging Commenced 7/12/85

Plugging Completed 7/15/85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Former  
LEASE OPERATOR W.D. Short

ADDRESS Box 45, Oxford, Kansas, 67119

PHONE 316 455-3694 OPERATORS LICENSE NO. 6679

Character of Well SWD  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? No If not, Is well log attached? yes

Producing formation Wellington Salt Depth to top 235 bottom 412 T.D. 412

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation         | Content     | From       | To         | Size         | Put in     | Pulled out |
|-------------------|-------------|------------|------------|--------------|------------|------------|
| <u>Wellington</u> | <u>Salt</u> | <u>235</u> | <u>412</u> | <u>4 1/2</u> | <u>231</u> | <u>0</u>   |
|                   |             |            |            | <u>8 5/8</u> | <u>120</u> | <u>0</u>   |
|                   |             |            |            |              |            |            |
|                   |             |            |            |              |            |            |
|                   |             |            |            |              |            |            |

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Tried to run 2" tubing & stopped at 35'  
Run 1" tubing to 135 feet & it stopped and would not go any deeper.  
Cemented to surface with 13 sacks of cement then pulled 1" tubing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor W.D. Short License No. 6679  
Address Box 45, Oxford, Kansas, 67119

STATE OF Kansas COUNTY OF Sumner, ss.

W.D. Short (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.D. Short

(Address) Box 45, Oxford, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
JUL 18 1985

AND SWORN TO before me this 16 day of July, 1985  
Margie A. Short  
Notary Public

My Commission expires: Oct. 16, 1988

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

15-173-19093-0001

2

COMPANY Pickrell Drilling Co.  
FARM Struthers A<sup>n</sup> NO. 1 SWD

SEC. V T. 29 R. 2W  
LOC. NE NE SW

TOTAL DEPTH

COMM.

SHOT OR TREATED

CONTRACTOR

ISSUED

CASING

20

15

12

13

10

8 5/8" - 120' cemented with 100 sacks

6 1/2" - 250' cemented with 200 sacks


5 1/2" - 3" cement lined tubing inside of 5 1/2" for injection string

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION

PRODUCTION

COUNTY Sedgwick  
KANSAS



Surface, soil & shale

0 - 120'

Shale

120 - 250'

Salt

250 - 350'

Shale

350 - 427' T. D.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1965

CONSERVATION DIVISION  
Wichita, Kansas