

15-173-01214-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Sedgewick County. Sec. 2 Twp. 29 Rge. 2W (E) (W)

Location as "NE/CNW/SW" or footage from lines. CN $\frac{1}{2}$ N $\frac{1}{2}$ SW

Lease Owner Pickrell Drilling Co.

Lease Name Struthers Well No. "A" # 2

Office Address 2820 Paseo, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed yes 19____

Application for plugging approved yes 19____


Plugging commenced 6-5-60 19____

Plugging completed 6-11-60 19____

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Percy Hall

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3596' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>4 1/2"</u>	<u>3 581</u>	<u>2625'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 6-5-60. Plugging completed 6-11-60. Measured into total depth, 3596'. Plugged off bottom: Sanded back up hole to 3570' and dumped 5 sacks of cement. Worked and shot casing. Shot 4 1/2" casing at 2625'. Worked pipe free. Pulled and laid down casing. Plugged well: Mudded hole up to 250'. Set a 20' rock bridge. Dumped 15 sacks of cement. Mudded hole up to 35'. Set a 5' rock bridge. Capped the well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1960
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1960

My commission expires December 8th, 1963

Kayann Jenkins
Kayann Jenkins
Notary Public.



15-173-01214-0000

WELL LOG

R

COMPANY **PICKRELL DRILLING COMPANY**

SEC. 2 T. 29S R. 2W

FARM **STRUTHERS "A" NO. 1**

LOC. **SE, NW, SW**

*2-29-2
Sand and shale*


TOTAL DEPTH **3595'**

COUNTY **Sedgwick Co., Kansas**

COMM. **July 15, 1957**

COMP. **July 26, 1957**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 448' W/275 sax.
4 1/2" @ 3581 W/150 sax.**

ELEVATION **1372' DF**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

253	Sand & shale
260	Salt
449	Salt, shale & shells
2185	Shale & lime
2370	Shale & shells
3015	Lime & shale
3162	Lime
3595	Lime & shale
3595	T. D.

State of KANSAS)
County of BARTON) AS:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Struthers well

Verne A. Morris

Subscribed and sworn to before me this 5th day of August 19 57

My Commission Expires: July 11, 1960

Red J. Brown
NOTARY PUBLIC