


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 1 Twp. 29 Rge. 2W (X) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Petroleum, Inc.
Lease Name WISE Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 18 1955
Application for plugging filed July 18 1955
Application for plugging approved July 18 1955
Plugging commenced July 18 1955
Plugging completed July 18 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Duerke
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	186'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 180' followed by
wooden plug. Placed 15 sacks cement through drill
pipe onto plug. Mudded up to 20' followed by 2nd
wooden plug and 5 sacks cement to base of well cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 X 1955

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker
311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of July, 1955

My commission expires 10-27-56
Marjorie Bradshaw Notary Public.

PLUGGING
FILE SEC 1 T 29 R 2W
BOOK PAGE 137 LINE 1

WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **1** T. **29S** R. **2W**

FARM **WISE**

NO. **1**

LOC. **NE NE NE**

TOTAL DEPTH **3940'**

COUNTY **Sedgwick**

COMM. **July 6, 1955**

COMP. **July 18, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 186' w/175 sax**

ELEVATION **1315' DF**
1318' RB

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

130	Sand
315	Shale
320	Anhydrite
675	Lime & Shale
915	Shale & Lime Streaks
2450	Shale & Lime
2645	Shale
2709	Lime
2887	Lime & Shale
2987	Lime
3052	Lime & Shale
3120	Lime
3415	Shale & Lime
3485	Shale
3498	Mississippi
3546	Lime
3733	Mississippi Lime
3830	Lime & Shale
3860	Simpson
3899	Lime & Shale
3930	Lime
3940	Arbuckle

Geological Tops

Heebner:	2264 (- 946)
Stalnaker:	2576 (-1258)
Kansas City	2875 (-1557)
Base Kansas City:	3072 (-1754)
Mississippi:	3482 (-2164)
Simpson:	3811 (-2493)
Arbuckle:	3902 (-2584)


R.T.D. 3940'

RECEIVED
 JUN COMMISSION
 AUG 5 X 1955
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of SEDGWICK } SS:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the WISE #1 well



Subscribed and sworn to before me this 22nd day of July 19 55

My Commission Expires: 8-11-58

Karl E. Becker

 NOTARY PUBLIC