


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County. Sec. 18 Twp. 30 Rge. (E) 2 (W) 2
Location as "NE/CNW/SE/SW" or footage from lines: N/2 NW SE NW
Lease Owner: Shawver Armour, Inc.
Lease Name: Duncan Well No. 2
Office Address: 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 16 19 64
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3284 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	-0-	242'	8 5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole with 40 Vis. mud to 200'
Set a dry hole plug -
Added 1/2 sack hulls and 15 sacks cement
Mudded hole to 30'
Set a dry hole plug
Added 1/4 sack hulls and 8 sacks cement
Mudded Rat hole to 8' of surface and
dumped 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Shawver Armour, Inc.
Address: 817 Central Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour, 817 Central Bldg.
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 64

My commission expires December 10th, 1967

Claire Jones
Notary Public.



DRILLER'S LOG

FARM NAME: DUNCAN # 2 LOCATION: N/2 NW SE NW 18-30-2W
 Sumner County, Kansas
 CONTRACTOR: SHAWVER ARMOUR, INC. ELEVATION: 1369 KB
 OWNER: SHAWVER ARMOUR, INC.
 COMMENCED: January 8, 1964 COMPLETED: January 16, 1964
 CASING RECORD: 242' 8 5/8" w/165 sx cement & 4 sacks CC

FORMATION:TOPS:

Gray Shale	242	Stalnaker	2790
Shale	280	Kansas City	3104
Shale & Lime	535		
Lime & Shells	645		
Lime & Shale	875		
Shale & Lime	1155		
Lime & Shale	1635		
Shale & Lime	1795		
Lime & Shale	1990		
Lime	2045		
Shale & Lime	2120		
Lime & Shale	2595		
Shale	2620		
Lime	2707		
Lime & Shale	2790		
Stalnaker Sand	2922		
Shale I	3020		
Shale & Lime	3089		
Kansas City	3179		
Kansas City Lime	3284		
Rotary Total Depth	3284		

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 23 1964
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 SEDGWICK COUNTY) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
 James M. Armour

Subscribed and sworn to before me this
 21st day of January, 1964.

My commission expires Dec 10th, 1967

Claire Jones
 Claire Jones, Notary Public