


15-191-01484-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Summer County. Sec. 16 Twp. 30 Rge. (E) 2 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 N.W./4 N.W./4
Lease Owner Eckland Drilling Company
Lease Name Love Well No. 2
Office Address 218 Bissantz Building
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 10th 19.50
Application for plugging filed March 10th 19.50
Application for plugging approved March 10th 19.50
Plugging commenced March 10th 19.50
Plugging completed March 10th 19.50
Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3294 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 84' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to bottom of surface pipe
Put plug in at 80 feet cementing with 15 sacks cement
filled on up with mud and topped with 10 sacks of cement

MAR 17 1950 3-17-50

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to ECKLAND DRILLING COMPANY
Address 218 Bissantz Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
P. A. Eckland (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. A. Eckland

My Commission Expires: 11-18-52 (Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 19.50
C. L. Madew Notary Public

My commission expires Nov 18-52

22-5138-s 9-48-10M

PLUGGING
FILE SEC 16 T 30 R 20
BOOK PAGE 41 LINE 41

LOCATION: Love #2
NW/4 NW/4 Sec.16-30-2W
Sumner County, Kansas

COMPANY: Turpin and Porter
Contractor: Eckland Drilling Co.

Casing: 84' 8 5/8"
65 sacks cement

Commenced: 2-27-50
Completed: 3-10-50

ROTARY DEPTH: 3294

| | | | |
|------|----------------------------|------|----------------|
| 80 | shale and shells | | |
| 480 | shale and shells | 3147 | lime |
| 495 | anhydrite | 3256 | lime |
| 510 | shale and lime | 3275 | lime |
| 635 | lime and shale | 3294 | lime and shale |
| 670 | anhydrite and shale | 3294 | T. D. |
| 840 | lime and shale | | |
| 960 | anhydrite and shale | | |
| 1045 | anhydrite, lime, and shale | | |
| 1115 | shale and shells | | |
| 1235 | lime and shale | | |
| 1370 | lime and shale | | |
| 1630 | shale and shells | | |
| 1740 | shale and shells | | |
| 1820 | shale, sand and lime | | |
| 1838 | lime and shale | | |
| 1850 | lime and shale | | |
| 2003 | lime | | |
| 2160 | lime | | |
| 2180 | shale | | |
| 2250 | lime | | |
| 2265 | sandy lime | | |
| 2315 | lime and shale | | |
| 2335 | sand and lime | | |
| 2355 | lime, shale and sand | | |
| 2400 | sandy lime | | |
| 2455 | lime and shale | | |
| 2590 | lime and shale | | |
| 2675 | lime and shale | | |
| 2800 | shale and lime | | |
| 2825 | shale and lime | | |
| 2862 | sandy lime | | |
| 2902 | lime and shale | | |
| 2910 | sandy shale | | |
| 2965 | shale and lime | | |
| 3035 | shale and lime shell | | |
| 3079 | shale and shells | | |
| 3098 | lime K. C. | | |
| 3157 | lime | | |
| 3174 | lime and shale | | |
| 3195 | lime | | |

RECORDED
MAR 17 1950

Top of Kansas City 3039
Total depth 3294

SEC-16, 30, 2W
SUMNER COUNTY, KANSAS
ECKLAND DRILLING CO.