

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County. Sec. 16 Twp. 30 Rge. XX 2 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Messman-Rinehart Oil Company

Lease Name Orie Love Well No. 1

Office Address 518 Petroleum Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed October 28 19 58

Application for plugging filed October 28 19 58

Application for plugging approved October 28 19 58


Plugging commenced October 28 19 58

Plugging completed October 28 19 58

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Forest Hagar

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3797 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 283 | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 200 ft. Wooden plug at 200 ft. with 1/4 sack hulls and 15 sacks cement on plug. Hole filled with heavy rotary mud to 40 ft. Wooden plug at 40 ft. with 1/4 sack hulls and 10 sacks cement on plug.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1958
11-8-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc., -License #209

Address Box 448 El Dorado, Kansas


STATE OF Kansas, COUNTY OF Butler, ss.

Dale R. Daniel, employee of contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel

Box 448 El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 58



Ernest Liffard Notary Public.

My commission expires April 21, 1960

PLUGGING
FILE SEC. 16 T. 30 R. 20
BOOK PAGE 142 LINE 19

Casing Record.

8 5/8

283' cemented
w/185 sacks

Location: SE/4 SE/4 NW/4

Section: 16-30S-2W

Sumner County, Kansas

Farm: Ori. Love #1

Well Owner: Messman-Rinehart Oil Co.

Contractor: White & Ellis Drilling, Inc.

Started: 10-17-58

Completed: 10-28-58

T.D.

3797'

Kelly bushing measure 5' above ground level:

| <u>FORMATION</u> | <u>DEPTH</u> | <u>Figures indicates bottom of formation</u> |
|--------------------|--------------|--|
| Sand & red Clay | 0-4 | |
| Sand | 75 | |
| Sandy Shale- | 130 | |
| Shale & Lime stks. | 283 | Dry Hole |
| Shale & Shell | 535 | |
| Lime | 670 | Plugged & Abandoned |
| Shale & Lime | 750 | |
| Shale & Shell | 880 | |
| Lime & Shale | 960 | |
| Sandy Lime | 1036 | |
| Lime & Shale | 1070 | |
| Shale & Lime stks. | 1080 | |
| Shale & Lime stks. | 1350 | |
| Lime & Shale | 1410 | |
| Shale & Shell | 1705 | |
| Lime & Shale | 1845 | |
| Lime & Shale stks. | 1920 | |
| Shale & Lime stks. | 2125 | |
| Lime | 2170 | |
| Shale & Shell | 2210 | |
| Lime | 2240 | |
| Shale & Lime | 2280 | |
| Sand | 2420 | |
| Sandy Shale | 2480 | |
| Lime & Shale stks. | 2550 | |
| Shale & Lime | 2675 | |
| Shale & Shell | 2834 | |
| Sand | 2873 | |
| Shale & Lime | 3034 | |
| Shale w/Lime stks. | 3080 | |
| Lime, Lansing | 3112 | |
| Lime, Kansas City | 3284 | |
| Shale & Lime | 3390 | |
| Lime | 3410 | |
| Shale & Lime | 3493 | |
| Lime | 3534 | |
| Shale & Lime | 3695 | |
| Lime, Mississippi | 3797 | |

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1958

CONSERVATION DIVISION
Kansas

PLUGGING

FILE SEC. 16 T. 30 R. 2W

BOOK PAGE 142 LINE 19