

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sumner SEC. 19 TWP. 30S RGE. 3W E/W
Location as in quarters or footage from lines:
NE NE NE

Lease Owner Dunne-Gardner Petroleum, Inc.
Lease Name Small #1 Well No. _____
Office Address 200 W. Douglas Suite 250 Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3-5-82
Plugging completed 3-15-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Tim Galliher
Producing formation _____ Depth to top _____ bottom T.D. 4350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	213'	none
				5-1/2"	4210'	2847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3800' and ran 5 sacks cement. Shot casing @3260',
XXXXX, 3142', 3021', 2943' and 2855'. Pulled a total of 65 joints of pipe. Set rock-
bridge @230' to 215' and dumped 5 sacks cement, run 3-1/2 yards ready-mix cement
from 215' to base of cellar.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1982



My Commission expires:

[Signature]
Notary Public.

DRILLERS LOG

#1 SMALL
 NE NE NE Section 19-30S-3W
 Sumner County, Kansas

OPERATOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
 Suite 250, 200 West Douglas
 Wichita, Kansas 67202

COMMENCED: February 23, 1979

COMPLETED: March 5, 1979

CASING RECORD: 8-5/8" @ 213' w/175 sx
 5-1/2" @ 4210' w/200 sx latex

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	217	Sand and shale
217	820	Shale
820	3445	Lime and shale
3445	3685	Lime
3685	3830	Lime and shale
3830	3889	Lime
3889	3914	Lime and shale
3914	4350	Lime
4350		Rotary total depth

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt
 Donald E. Hunt

Subscribed and sworn to before me this 14th day of March, 1979.

My appointment expires: Notary Public
 January 4, 1981