


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

_____ Sumner County. Sec. 15 Twp. 30S Rge. 36E (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SE¹/₄ SE¹/₄ NW¹/₄
Lease Owner Aurora Gasoline Company
Lease Name Lange Well No. 1
Office Address 802 Union Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10/19 19 56
Application for plugging filed 10/19 19 56
Application for plugging approved 10/19 19 56
Plugging commenced 10/19 19 56
Plugging completed 10/19 19 56
Reason for abandonment of well or producing formation No Production

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil and Sand	Fresh Water	42'	54'	8 5/8"	270'	Left in, Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 3960' - 180'
Halliburton Plug with 15 Sacks Cement
Mud to 30'
Halliburton Plug with 10 Sacks Cement
Steel Plate Welded on Top

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Criswell Drilling Company
Address First National Bank Building, Winfield, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.
John Christensen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 916, Winfield, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of October, 19 56

My commission expires August 20, 1959

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1956
10-30-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 T. 30 R. 3W
BOOK PAGE 109 LINE 25

WELL LOG

Company: Aurora Gasoline Company
 Farm: Lange
 Total Depth: 3960'
 Comm. 10/7/56 Comp. 10/19/56
 Shot or Treated:
 Contractor: Criswell Drilling Company
 Issued:
 Casing: 8 5/8"

Sec. 15, Twp. 30S, Rge. 3W
 Loc. SE $\frac{1}{4}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$
 Sumner County, Kansas

Elevation:
 Production:

FIGURES INDICATE BOTTOM OF FORMATIONS

290 - Lime Shells	3383 - Lime and Shale
500 - Shale and Shells	3440 - Lime
840 - Shale and Lime	3510 - Shale and Lime
1010 - Lime and Shale Streaks	3545 - Shale and Lime
1135 - Lime	3611 - Shale W/Lime
1260 - Lime	3686 - Shale and Lime
1270 - Shale	3743 - Shale and Lime
1380 - Lime and Shale	3786 - Shale W/Lime
1410 - Lime and Shale	3818 - Shale
1595 - Shale and Lime	3836 - Mississippi (Lime and Shale)
1815 - Shale and Lime	3876 - Lime and Shale
1975 - Shale and Lime Streaks	3911 - Lime
2015 - Shale and Lime	3960 - Lime W/Shale
2225 - Shale and Lime	
2365 - Shale and Lime	
2430 - Shale and Lime	
2470 - Sandy Lime	
2535 - Lime and Shale Sdy.	
2678 - Shale and Lime	
2800 - Shale and Lime	
2910 - Shale and Lime and Sand	
3020 - Sand, Stal. Zone	
3065 - Shale	
3120 - Shale	
3183 - Shale	
3207 - Shale	
3218 - Lime	
3230 - Core # 1	
3239 - Sandy Lime	
3292 - Lime	
3340 - Lime	

I, John Christensen, of the Criswell Drilling Company, certify the above rotary log to be true and correct.

CRISWELL DRILLING COMPANY


 John Christensen, Owner

RECEIVED
 STATE CORPORATION COMMISSION

OCT 30 1958

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING	
FILE	SEC. 15 T. 30 R. 3W
BOOK	PAGE 109 LINE 25