15-191-30021-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sumner County. Sec. 11 Twp. 30S Rge. 3W (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines C SW NW

Lease Owner Leben Drilling, Inc.

Lease Name ~~XXXXXXXXX~~ Schroeder Well No. 1

Office Address Box 486, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-8--65 19

Application for plugging filed 4-8-65 19

Application for plugging approved 4-8-65 19

Plugging commenced 4-8-65 19

Plugging completed 4-8-65 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin, Clearwater, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3845 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 225' ½ sk. hulls Plug added 20 sks. cement
Mud to 30' Added ½ sk. hulls Plug bridged added 8 sks. cmnt.

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1965
4-13-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 65

Notary Public.

My commission expires April 1, 1967

15-191-30021-0000

DRILLER'S LOG

COMPANY:	Leben Drilling, Inc.
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	SCHROEDER #1
LOCATION:	C SW NW Sec. 11-30S-3W SUMNER COUNTY, KANSAS
COMMENCED:	3-29-65
COMPLETED:	4-8-65

0	256	Shale & Gypsum
256	450	Shale & Lime
450	1360	Lime & Shale
1360	2695	Shale & Lime
2695	2881	Sandy Shale & Lime
2881	3015	Sand
3015	3185	Lime & Shale
3185	3845	Lime
	3845	RTD - D & A

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1965
CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" used surface casing @ 256' cemented with 190 sacks 60-40 Posmix Sunset 2% Gel

---

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schroeder #1 well, located C SW NW of Section 11, Township 30 South, Range 3 West, Sumner County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 12th day of April, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires
April 1, 1967