

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Sumner County. Sec. 9 Twp. 30S Rge. 3 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE/4 - SE/4 - NE/4
Lease Owner Blackwell Oil & Gas Company
Lease Name W. D. Little Well No. 1
Office Address Box 911, Cushing, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/3 - 19 55
Application for plugging filed 6/3 - 19 55
Application for plugging approved 6/3 - 19 55
Plugging commenced 6/4 - 19 55
Plugging completed 6/4 - 19 55
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation Depth to top Bottom Total Depth of Well 4440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	240'	
				Surface Casing		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to bottom of surface pipe, set Halliburton plug, 15 sacks of cement, filled hole to 25' with heavy mud, set Halliburton plug, cemented with 10 sacks of cement, welded steel plate on top of surface pipe.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Springer & Harper
Address Valley Center, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Harper Partner
Valley Center, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June 19 55
Edward S. Greider
Notary Public.

My commission expires Jan. 31, 1957

24-7968-S 3-53-20M



SPRINGER & HARPER

DRILLING CONTRACTORS
VALLEY CENTER, KANSAS

June 6 1955

BLACKWELL OIL & GAS COMPANY
P. O. Box 911
Cushing, OklahomaW. D. LITTLE NO. 1
SE/4 - SE/4 - NE/4, Sec. 9, Twp., 30
South, Range 3 West, Sumner County,
Kansas.

TOP SOIL & CLAY	0 - 33
lime	120
lime & shale	200
shale & shells	240
shale & shells	630
lime & shale	695
lime	780
salt	860
shale & lime	985
lime	1015
lime & shale	1090
lime	1145
lime & shale	1195
lime	1430
lime & shale	2110
lime	2150
lime & shale	2195
lime	2310
lime & shale	2424
sand	2521
shale & lime	2565
shale	2570
lime	2680
shale	2930
sand	3030
sand & shale	3045
shale	3202
lime	3430
lime & shale	3693
lime	3717
shale	3756
shale & lime	3826
shale	3830
lime	4165
lime & shale	4213
shale	4260
shale & lime	4296
sand	4320
sand & shale	4402
lime	4440

T.D.

CASING240 ' of 10 3/4", 32#
Surface Casing was run and
was cemented w/200 sacks of
bulk cement.

TOPS: 3210	K.C. Lime
3823	Mississippian
4300	Simpson Sand
4403	Arbuckle Lime

RECEIVED
DATE FOR CONT. WORK
JUL 1 1955CONCRETE DIVISION
Wichita, Kansas

PLUGGING

FILE	SEC	9	T	30	R	34
BOOK	PAGE	124	LINE	25		

SPRINGER & HARPER

By L. L. Harper
L. L. HARPER (Partner)