

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Neal

NORTH



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 16 Twp. 29 Rge. (E) 1 (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Smith Bros. Oil Co.
Lease Name Parker Well No. 1
Office Address 1005 Union Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 9/04/64 19
Application for plugging filed 9/05/64 19
Application for plugging approved 9/05/64 19
Plugging commenced 9/05/64 19
Plugging completed 9/05/64 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation Depth to top Bottom Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 210', set dry hole plug, added 1/2 sx. hulls and 20 sx. cement.
Mud to 30', set a plug, added hulls and 8 sacks cement.
Capped rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1964 9-14-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling Co.
Address 324 No. Orchard, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Harry Hughes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Harry Hughes

(Address)

SUBSCRIBED AND SWORN to before me this

9

day of

August

1964

My commission expires

October 6, 1967

John F. Brown

Notary Public.

Triangle Drilling Co.
 Parker # 1
 SW SW SW Sec. 16-29-1W
 Sedgwick County, Kansas

WELL LOG

Commenced 8/19/64
 Completed 9/04/64
 R.T.D. 3960'
 Run 350' of 8 5/8" casing
 Cemented 250 sx.

0-----	10	Soil and sand
10-----	60	Sand
60-----	170	Clay - shale
170-----	230	Anhydrite shale
230-----	348	Lime - shale
348-----	480	Lime - shale bks.
480-----	630	Lime
630-----	1270	Shale - lime
1270-----	1450	Shale - lime stks.
1450-----	1570	Shale
1570-----	1771	Shale - lime
1771-----	1870	Lime and shale
1870-----	2748	Lime and shale
2748-----	2922	Lime and shale
2922-----	2960	K.C. Lime
2960-----	3015	Lime
3015-----	3070	Lime (KC)
3070-----	3134	KC. Lime
3134-----	3145	Shale and lime
3145-----	3595	Lime and shale
3595-----	3650	Lime (Miss.)
3650-----	3720	Lime Mississippi
3720-----	3805	Miss. Lime and shale
3805-----	3960	Lime and shale
3960-----		R. T. D.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 14 1964

CONSERVATION DIVISION
 Wichita, Kansas