


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4  
9

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

SEDGWICK County, Sec. 15 Twp. 29S Rge. 1W (E) 1W (W)



Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner E. H. ADAIR OIL COMPANY  
Lease Name MAECHTLEN Well No. 2  
Office Address P. O. BOX 7011, WICHITA, KANSAS 67201  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 10 OCTOBER 19 64  
Application for plugging filed 10 OCTOBER 19 64  
Application for plugging approved 10 OCTOBER 19 64  
Plugging commenced 10 OCTOBER 19 64  
Plugging completed 10 OCTOBER 19 64  
Reason for abandonment of well or producing formation DRY HOLE 10 OCTOBER 64

If a producing well is abandoned, date of last production NONE 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well PAUL TURPIN  
Producing formation NONE Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3776 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	SURFACE	345' RB	8 5/8" OD	339.93'	LEFT IN
(SEE ATTACHED LOG)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH 40 VISCOSITY DRILLING MUD TO 225', SET PLUG AND 1/2 SACKS HULLS AND  
CEMENTED WITH 20 SACKS CEMENT, FILLED HOLE WITH DRILLING MUD TO 35', SET PLUG AND HULLS  
AND CEMENTED WITH 8 SACKS CEMENT, PUT 2 SACKS CEMENT IN RAT HOLE.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 23 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor REX & MORRIS DRILLING COMPANY  
Address P. O. BOX 334, EL DORADO, KANSAS 67042

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
A. H. FISHER (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Fisher  
P. O. BOX 334, EL DORADO, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 21ST day of OCTOBER, 19 64

My commission expires 8 AUGUST 1966  
Elizabeth Deschner  
ELIZABETH DESCHNER Notary Public.

R

MARSHLEN # 2

E. H. Adair Oil Company

TOTAL DEPTH: 3776 RB  
CONTRACTOR: Rex & Morris  
COMMENCED: 10-2-64  
COMPLETED: 10-10-64  
INITIAL PROD.: D. & A.

LOCATION: NE SE NW  
SECTION 15-29S-1W  
SEDGWICK COUNTY, KANSAS

CASING RECORD:  
8 5/8" OD @ 345' w/250 BAGGS

FORMATION	DEPTH
Surface Hole	345'
Lime and Shale	885'
Shale and Lime	2080'
Lime and Shale	2765'
Shale and Lime	2912'
Lime	3025'
Lime and Shale	3415'
Lime	3675'
Lime and Shale	3772'
Simpson Sand	3776'

RED

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 23 1964  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By A. H. Fisher  
A. H. Fisher

STATE OF KANSAS  
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 21st day of October, 1964.

Elizabeth Deschner  
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1966.

3772