


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sedgwick County. Sec. 15 Twp. 29 Rge. 1 EW
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE/NE/NE
Lease Owner Continental Oil Company
Lease Name O.S.A. Unit Well No. 11
Office Address Box 267, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ May 19 1977
Plugging completed _____ June 9 1977
Reason for abandonment of well or producing formation _____
depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ted E. Dewey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3741'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	309'	none
				4 1/2"	3725'	2,484.87'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.


Dumped sand to 3650' and 4 sacks cement.
Shot pipe at 3250', 3100', 2900', 2700' and 2515'.
Pulled a total of 77 joints of 4 1/2" casing.
Sun Cementing plugged well with 3 sacks hulls, 15 sacks gel and
100 sacks common cement with 376 lbs. added gel.

RECEIVED
CONSERVATION COMMISSION
JUN 14 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 13th day of June, 1977

My commission expires May 21, 1980

Marla K. Haslam
Marla K. Haslam Notary Public

ROY #5

Casing Record: Company: Aylward Drilling Company Location: NE NE NE
 8 5/8" - 309' Contractor: Aylward Drilling Company Section 15-29-1W
 4 1/2" - 3725' Commenced: April 25, 1964 Sedgwick County
 Completed: May 6, 1964 Kansas

Elevation: 1293 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Surface Clay	0	30	Set 8 5/8" surface pipe @ 309' w/300 sacks cement.	
Sand	30	60		
Lime	60	715	Geological Tops:	
Lime & Shale	715	2070		
Lime	2070	2195		
Shale & Lime	2195	2463		Stalnaker 2454
Shale	2463	2500		Kansas City 2783
Shale & Sand	2500	2613		Base Kansas City 2993
Shale & Lime	2613	2781		Mississippi 3342
Lime	2781	3230		Kinderhook 3652
Lime & Shale	3230	3360		Simpson 3716
Lime	3360	3741 T.D.		

DST 3720-41 Open 70"
 Rec. 380' oil, 60' MCO, 60' O&GCM
 IBHP 1075#/30" - FBHP 1075#/30"
 FP 45#-171#

Set 4 1/2" casing @ 3725' w/75 sacks.

RECEIVED
 STATE CORPORATION COMMISSION

APR 27 1977

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 11th day of May, 1964

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1965