


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sedgwick County. Sec. 12 Twp. 29 Rge. 1 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SW SE NW
Lease Owner Beardmore Drilling Company
Lease Name Curless Well No. 1
Office Address 827 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-24 19 57
Application for plugging filed 1-24 19 57
Application for plugging approved 1-24 19 57
Plugging commenced 1-24 19 57
Plugging completed 1-24 19 57
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Clays & Sands		0	155'	8-5/8"	155'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 0 to 35' - 10 sacks cement
- 35' - Wood Plug
- 35' to 105' - Heavy Mud
- 105' to 150' - 15 sacks cement
- 150' - Wood Plug
- 150' to 3350' - Heavy Mud

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Renfro Drilling Company
Address Insurance Building, Wichita, Kansas.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Heber Beardmore (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
827 Beacon Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 57

My commission expires January 28, 1960
RECEIVED STATE CORPORATION COMMISSION
Leonard P. Tolle Notary Public.

PLUGGING
FILE SEC. 12, T. 29, R. 1, W. _____
BOOK PAGE 136, LINE 13
FEE: 1957 2-1-57
CONSERVATION DIVISION
Wichita, Kansas

OPERATOR - BEARDMORE DRILLING COMPANY
 WELL - CURLESS #1
 LOCATION - SW SE NW Section 12-29S-1W
 Sedgwick County, Kansas
 CONTRACTOR - Renfro Drilling Co.
 COMMENCED - 1-15-57
 COMPLETED - 1-24-57
 CASING - 8 5/8" @ 155' with 125 sacks cement
 ELEVATION - 1294 Rotary Bushing

DRILLERS' LOG

155 - 270	Shale and lime
270 - 540	Lime and shale
540 - 800	Shale and shells
800 - 1053	Lime and shale
1053 - 1100	Lime and shale
1100 - 1145	Shale and shells
1145 - 1725	Shale and shells
1725 - 1920	Shale and lime
1920 - 2090	Lime and shale
2090 - 2275	Lime and shale
2275 - 2435	Shale and lime
2435 - 2530	Shale and sand
2530 - 2600	Shale and lime
2600 - 2746	Shale
2746 - 2833	Lime
2833 - 2895	Lime
2895 - 2938	Lime
2938 - 2949	Shale
2949 - 3049	Shale and lime
3049 - 3139	Lime and shale
3139 - 3207	Lime and shale
3207 - 3269	Lime and shale
3269 - 3286	Lime and chert
3286 - 3305	Coring
3305 - 3316	Coring
3316 - 3326	Coring
3326 - 3350	Lime
3350 -	Total Depth

STATE OF KANSAS)
)ss
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By Henry S. Finken

Subscribed and sworn to before me this 28th day of January, 1957.

My commission expires May 4, 1959.

RECEIVED
 STATE CORPORATION
 Notary Public
 FEB 1 1957

PLUGGING
 FILE SEC. 12 T. 29 R. 1W
 BOOK PAGE 136 LINE 12

CONSERVATION DIVISION
 Wichita, Kansas