

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T 29S NORTH R 1W

	12		
	*		

Locate well correctly on above
Section Plat

Sedgwick County. Sec. 12 Twp. 29S Rge. 1 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW.
Lease Owner Beardmore Drilling Company
Lease Name Smith Well No. 1
Office Address 827 Beacon Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-25 1956
Application for plugging filed 2-21 1957
Application for plugging approved 2-23 1957
Plugging commenced 3-1 1957
Plugging completed 3-4 1957
Reason for abandonment of well or producing formation non-commercial
If a producing well is abandoned, date of last production 2-19 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Mississippi Depth to top _____ Bottom _____ Total Depth of Well 3316 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	158'	None
				5-1/2"	3303'	2301'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3316' to 3275' and ran 6 sacks of cement. Mudded the hole to 150', set a 10' rock bridge and ran 30 sacks of cement. Mudded the hole to 20', set a 10' rock bridge and ran 8 sacks of cement to the base of the cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BEARDMORE DRILLING COMPANY


(Signature) By Heber Beardmore827 Beacon Building, Wichita, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1957Leonard P. Tolle

Leonard P. Tolle

Notary Public.

My commission expires January 28, 1960

BEARDMORE-SUTTON-KIOWA
#1 Smith
SE SE SW Section 12-29S-1W
Sedgwick County, Kansas

Drilled By: Beardmore Drilling Co.
Drilling Commenced: 6-17-56
Drilling Completed: 6-25-56

Casing Record:

Ran 160' of 13-3/8" pipe set at 158' with 175 sacks cement.
Cement circulated: 6-17-56.
5-1/2" pipe set at 3303' with 50 sacks cement. 6-25-56.

Elevations: KB 1291
DF 1289
Gr 1287

<u>FORMATIONS</u>	<u>DEPTH</u>
Shale	35
Sand	70
Shale and Shells	158
Shale and Shells	270
Lime	305
Lime and Shale	775
Lime and Shale	1940
Lime and Shale	2850
Lime	2915
Lime and Shale	3090
Lime and Shale	3300
Rotary Total Depth	3315
Cable Tool Total Depth	3316

TOPS

Kansas City 2748
Mississippi 3287

DRILL STEM TEST #1 - 3292-3300 Shut in 15 minutes, open 1 hour, good blow, shut in 15 minutes. 1680' of gas in pipe, recovered 10' of mud. Initial shut in pressure failed to work. FBHP 1125, IF 7, FF 7.

CORE #1 3300-3315 - recovered 15'.

DRILL STEM TEST #2 - 3303-3315 Shut in 15 minutes, open 1 1/2 hours, shut in 15 minutes. Weak blow first 1/2 hour of test as tool was plugged, good blow last hour. Recovered 1050' of gas in pipe, 95' of oil and gas cut mud. IBHP 1275, FBHP 900, IF 0, FF 270.

STATE OF KANSAS }
COUNTY OF SEDGWICK) ss

I, the undersigned, being first duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Robert J. Gulas

Subscribed and sworn to before me this 14th day of July, 1956.

Leonard P. Tolle

Leonard P. Tolle-Notary Public

My Commission Expires:
January 28, 1960

