


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Biting Building  
 Wichita, Kansas

WELL PLUGGING RECORD



Sedgwick County, Sec. 11 Twp. 29S Rge. 1 (E) W (W)  
 Location as "NE/CNW%SW%" or footage from lines NW SE SE  
 Lease Owner Beardmore Drilling Company  
 Lease Name Capron Well No. 1  
 Office Address 827 Beacon Building, Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed March 14 1955  
 Application for plugging filed March 13 1955  
 Application for plugging approved March 13 1955  
 Plugging commenced March 14 1955  
 Plugging completed March 14 1955  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3347 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil		0	20'	2 1/2"		
Sand		20'	75'	7 1/2"		
Shale & Shells		75'	150'	8 5/8"	150'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

150' to 3347' - Heavy Mud  
150' - Wood Plug  
105' to 150' - 15 sacks cement  
35' to 105' - Heavy Mud  
35' - Wood Plug  
0' to 35' - 5 sacks Cement

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Beardmore Drilling Company  
 Address 827 Beacon Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Heber Beardmore (~~employee of~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1955

Leonard P. Tolle  
 Notary Public.

My commission expires January 28, 1956

PLUGGING  
 FILE NO. 117-29S-1W  
 DEPT. PAGE 105 LINES 1

CAPRON #1

NW SE SE, Sec. 11-29S-1W  
Sedgwick County, Kansas.

Drilled for: Beardmore, Sutton &  
Drilled by: Beardmore. Kiowa

Casing Record:  
150' 8-5/8" w/115 sacks

Drilling Commenced: 2-23-55.  
Drilling Completed: 3-13-55

Elevations: KB 1290  
DF 1287  
Gr 1284

<u>FORMATIONS</u>	<u>Depth</u>
Cellar	5
Sandy Soil	20
Sand	7575
Shale & Shells	150
Lime	255
Lime	270
Lime	400
Lime	690
Shale & Lime	1215
Shale & Lime	1905
Shale & Lime	2075
Lime	2090
Shale & Lime	2240
Shale & Lime	2565
Shale & Lime	2810
Lime	2865
Shale & Lime	2955
Shale & Lime	3195
Shale & Lime	3293
Lime	3327
Total Depth	3347

TOPS:

Kansas City	2750
Conglomerate	3281
Mississippi	3285

CORE #1: 3293-3310

CORE #2: 3310-3326

CORE #3: 3327-3347

D&A

RECEIVED  
MAR 26 1955  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

*Ed Beardmore*

Subscribed and sworn to before me this 28th day of March, 1955.

*Leonard P. Tolle*  
Notary Public

My Commission Expires:  
January 28, 1956

**PLUGGING**  
FILE SEC 11 T 29 R 1W  
BOOK PAGE 105 LINE 1