

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

**Locate well correctly on above
Section Plat**

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

Sedgwick County. Sec. 11 Twp. 29S Rge. 1 (E) 1 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE-SE-SE

Lease Owner. Simpson Oil Company et al.

Lease Name. Capron Well No. 1

Office Address. 713 First Nat'l. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date, well completed. March 30 1934

Application for plugging filed. March 30 1934

Application for plugging approved. March 30 1934

Plugging Commenced. March 30 1934

Plugging Completed. March 30 1934

Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production. 1934

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Run drill pipe in hole, pumped heavy rotary mud in hole every 500 ft. while laying down drill pipe, set bridge at 257' at bottom of surface pipe, cement from 257' to 237', mud from 237' to 20', bridge set at 20', cement from 20' to 6', surface pipe cut off in bottom of cellar, steel plate welded over surface pipe, cellar filled with dirt to top of surface.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Simpson Oil Company
Address 713 First Nat'l. Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.

Sam Payne, Jr.

~~(employee of owner)~~ or (owner or operator) of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

713 First Nat'l Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April

19 42

My commission expires.....March 30, 1944

18-357

7-39—3M

Notary Public.

4-22-42
recd

CAPRON WELL NO. 1

Center SE 1/4 of SE 1/4 of SE 1/4 of Sec. 11-29S-1W, Sedgwick County, Kansas
 Owners: Continental Oil Company, W. N.
 Bartlett, L. A. Crum, Simpson
 Oil Company
 Casing Record: 8 1/4" @ 257'

Elevation:
 Total Depth: 3370'
 Commenced: 3--6-42
 Completed: 3-30-42 DRY

Log

Lime	75
Blue shale	215
Cave 215 lost circulation	
Lime	220
Shale & shells	257
Lime	410
Lime & shale	540
Red bed & lime	568
Lime	754
Lime & shale breaks	1030
Lime	1143
Shale & lime shells	1465
Shale & shells	1752
Lime broken	2124
Lime & shale	2305
Shale	2438
Lime & sandy lime	2490
Sandy lime	2550
Broken Shale & lime	2618
Shale & shells	2755
Lime K. C.	2773
Lime	2952
Shale	3052
Shale & lime shells	3194
Shale	3305
Lime	3370
Total Depth	3370

The undersigned, Sam Payne, Jr., of lawful age, and as Secretary of Simpson Oil Company does hereby certify that Simpson Oil Company drilled the above described well and that the above log is a true copy of the formations drilled as reflected by the daily drilling reports.

RECORDING	
FILE	11 29-42
BOOK	PAGE 29 LINE 19

Sam Payne, Jr.