




STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 11 Twp. 29S Rge. (E) 1 (W)
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner SHAWVER ARMOUR, INC.
Lease Name Linnebur
Office Address 877 Central Building, Wichita, Kansas Well No. 1
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 6 19 64
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3755 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	-0-	297	8 5/8"	297'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole w/44 Vis. mud to 200'
Set a dry hole plug - added 1/2 sack hulls add 15 sacks cement
Mudded hole from this point to 30'
Set w/plug added 1/4 sak hulls and 8 sacks cement
Capped rat hole w/2 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1964

4-14-64

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor SHAWVER ARMOUR, INC. (If additional description is necessary, use BACK of this sheet)
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
James M. Armour (operator or owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour, 817 Central Bldg.
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 64

My commission expires December 10, 1967

Claire Jones
Claire Jones Notary Public.



Q

DRILLER'S LOG

NAME: LINNEBUR # 1 LOCATION: NW SW NW Sec 11-29-1W
Sedgwick County, Ks.
CONTRACTOR: SHAWVER ARMOUR, INC. ELEVATION: 1299 KB
OWNER: SHAWVER ARMOUR, INC.
COMMENCED: March 24, 1964 COMPLETED: April 6, 1964
CASING RECORD: 297' 8 5/8" w/225 sack cement & 5 sacks cc

FORMATION:

TOPS:

Anhydrite 415
Lime & Shale 970
Shale 1495
Shale & Lime 2005
Lime & Shale 2195
Shale & Lime 2494
Stalnaker Sand 2585
Shale & Lime 2656
Shale 2801
Kansas City 2807
Lime 3024
Lime & Shale 3089
Shale & Lime 3353
Mississippian Dol. & Lm. 3406
Lime 3655
Kinderhook 3664
Shale 3721
Simpson 3755

Rotary Total Depth 3755

Iatan 2481
Stalnaker 2488
Kansas City 2801
Mississippian 3353
Kinderhook 3655
Simpson 3721

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
SEDGWICK COUNTY) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
James M. Armour

Subscribed and sworn to before me this
13th day of April, 1964.

My commission expires Dec 10, 1967

Claire Jones
Claire Jones, Notary Public