

15-173-03041-000/

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 3/22/62

LEASE NAME Gillian Unit \*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 14

\*Originally J.D. Gillian #2  
1650 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Gear Petroleum Co., Inc.

SEC. 33 TWP. 29 RGE. 1(X) or (W)

ADDRESS 1075 KSB Bldg. 125 N. Market Wichita, KS 67202

COUNTY Sedgwick

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 5151

Date Well Completed 3/22/68

Character of Well Input Docket # E19687

Plugging Commenced 1/29/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/29/90

The plugging proposal was approved on 1/23/90 (date)

by Steve VanGieson, Supervised by Dave Fritz (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Simpson Depth to Top 3747 Bottom 3753 T.D. 3753

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Simpson	Oil	3747	53	8 5/8	292	None
				5 1/2	3747	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sand back to 2653, dump 5 SX cement 2653 - 2610, perforate at 450' fill  
casing 0-450 and circulate to surface with 160 SX cement. Shut in pressure 100 PSI.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 1075 KSB Bldg. 125 N. Market Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 1075 KSB Bldg. 125 N. Market 67202

STATE CORPORATION COMMISSION

2-9-90


FEB 9 1990

SUBSCRIBED AND SWORN TO before me this 7 day of February, 19 90

CONSERVATION DIVISION  
Wichita, Kansas

Polly Tilton  
Notary Public

My Commission Expires: 8/1/93



D R I L L E R ' S   L O G

FARM NAME: GILLIAN # 2 LOCATION: SW NE SE SEC 33-29S-1W  
Sedgwick County, Kansas

CONTRACTOR: SHAWVER ARMOUR, INC.

OWNER: SHAWVER ARMOUR, INC. ELEVATION: 1259 K B  
LARIO OIL & GAS COMPANY

COMMENCED: March 10, 1962 COMPLETED: March 22, 1962

CASING RECORD: 292' 8 5/8" w/310 sacks cement & 7 sacks cc  
5 1/2" set @ 3747' cem w/100 sx reg.

## FORMATION:

## TOPS:

Anhydrite	350
Lime-Shale	1190
Shale-Shells	1490
Shale-Lime	2025
Lime-Shale	2445
Shale-Lime	2506
Stalnaker Sand	2658
Shale-Lime	2839
Kansas City Lime	2894
Lime	3049
Lime-Shale	3405
Mississippian Lime	3411
Lime	3694
Shale	3746
Simpson	3753

Stalnaker	2505
Kansas City	2839
Mississippian	3403
Simpson	3741

Rotary Total Depth 3753

STATE OF KANSAS)  
SEDGWICK County) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour  
James M. Armour

Subscribed and sworn to before me this  
28th day of March, 1962.

My commission expires Dec. 29th, 1963

+ Marjorie Hall  
Marjorie Hall, Notary Public