

15-191-01170-0000

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County, Sec. 36 Twp. 30 Rge. 2 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW
Lease Owner Beardmore Drilling Company
Lease Name Aufderhar Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-1-61 19
Plugging completed 12-4-61 19
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Al Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3782 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	None
				5-1/2"	3776'	2896'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3770', sanded to 3760' and dumped 5 sacks of ~~xxxxxxx~~ Cement @ 3760' with dump bailer. Pulled 5 1/2" casing. Set 10' rock bridge from 200' to 190' and ran 15 sacks of cement @ 190'. Mudded hole to 35', set 5' rock bridge to 30' and ran 10 sasks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE

DEC 12-19-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1961

My commission expires May 20, 1964
Milton J. Volin Notary Public.



9

BEARDMORE ET AL
#2 Aufderhar
SW SW SW Section 36-30N-2W
Sumner County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 2-8-58
Drilling Completed: 2-19-58

Casing Record:

Set 8-5/8" at 218' with 140 sacks cement on 2-8-58. Cement circulated.
Set 5-1/2" at 3776' with 75 sacks cement on 2-19-58.

Elevations: 1329 KB Est.
1327 DF
1325 Gr

<u>FORMATIONS</u>	<u>DEPTH</u>
Soil and cellar	20
Shale, Shells and Lime	218
Shale, Shells and Lime	630
Lime and Shale	2845
Sand	2900
Shale and Lime	3155
Lime	3300
Shale and Lime	3782
Rotary Total Depth	3782

TOPS

Kansas City	3090
Erosional Mississippi	3748
Mississippi Limestone	3756

DST #1 3218-3233 Shut in 20 min., open 1 hr., fair blow, shut in 20 min. Recovered 150' heavy oil cut mud. IEHP 800, FBHP 450, IF 45, FF 90, IH 1757, Temperature 105°.

CORE #1 3761-3771 Recover 10'

CORE #2 3771-3777 Recover 6'

CORE #3 3777-3782 Recover 5'

DST #2 3768-3782 Packer failed.

DST #3 3776-3782 Packer failed.

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1958

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SELDGWICK } ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Heb. Beardman

Subscribed and sworn to before me this 28th day of February, 1958.

Leonard P. Tolle
Leonard P. Tolle-Notary Public

My Commission Expires:
January 28, 1960

Top of Packer 3770'

Pipe Perforations From 3760' To 3766'

Q

BEARDMORE ET AL
#2 Aufderhar
SW SW SW Section 36-30S-2W
Sumner County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 2-8-58
Drilling Completed: 2-19-58

Casing Record:
Set 8-5/8" at 218' with 140 sacks cement on 2-8-58. Cement circulated.
Set 5-1/2" at 3776' with 75 sacks cement on 2-19-58.

Elevations: 1329 KB Est.
1327 DF
1325 Gr

<u>FORMATIONS</u>	<u>DEPTH</u>
Soil and cellar	20
Shale, Shells and Lime	218
Shale, Shells and Lime	650
Lime and Shale	2845
Sand	2900
Shale and Lime	3155
Lime	3300
Shale and Lime	3782
Rotary Total Depth	3782

<u>TOPS</u>	
Kansas City	3090
Erosional Mississippi	3748
Mississippi Limestone	3756

- DST #1 3218-3233 Shut in 20 min., open 1 hr., fair blow, shut in 20 min. Recovered 150' heavy oil cut mud. IBHP 800, FBHP 450, IF 45, FF 90, IH 1757, Temperature 105°.
- CORE #1 3761-3771 Recover 10'
- CORE #2 3771-3777 Recover 6'
- CORE #3 3777-3782 Recover 5'
- DST #2 3768-3782 Packer failed.
- DST #3 3776-3782 Packer failed.

RECORDED
INDEXED
FEB 23 1958
STATE DEPARTMENT OF COMMISSION
NOV 3 1958
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Leonard P. Tolle

Subscribed and sworn to before me this 28th day of February, 1958.

Leonard P. Tolle
Leonard P. Tolle-Notary Public

My Commission expires:
January 28, 1960