



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

5-22-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Voth of Raymond has this

date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company Inc.

Complete Address: 200 W. Douglas, Wichita, Kans.

Lease Name: Plains Townsite Well No. 1

Location: C SE SE Sec. 16 Twp. 32 Rge. 30 (W)

County: Meade Total Depth 5815' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

10 3/4" to 1590' circulated w/ cement. 7" to 5790' cemented.

Top perforations 5136' Plug bottom w/ 20 sacks cement

Top of cement 4860' Mud 4860' to 900'

Spot 40 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent