

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Myers of A.L. Abercrombie, Inc. has this date requested permission to plug the following described well:

Mr. Myers guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: B.H. Smith Well No. 1

Location: C NE NW Sec. 15 Twp. 32 Rge. 30 XX (E) (W)

County Meade Total Depth 5798' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Myers was instructed to plug the well as follows:

8 5/8" to 1592' circulated w/ cement. 5 1/2" to 5798' cemented.

Top perforations 5630' Plug bottom w/ 20 sacks cement

Top of cement 5530' Mud 5530' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edmund J. Enloe
Conservation Division Agent