



R

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Helmlly & has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Helmlly & Prather Oil Corporation

Complete Address: 518 Petroleum Bldg., Amarillo, Texas

Lease Name: Cottrell Well No. 1

Location: C SW SW Sec. 2 Twp. 32 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 5677' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1574' circulated w/ cement. 4 1/2" to 5677' cemented.

Top perforations 4788' Plug bottom w/ 20 sacks cement.

Top of cement 4600' Mud 4600' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent