

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Kelso of Sinclair Oil & Gas Co. has this
 date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Sinclair Oil & Gas Co.

Complete Address: Box 521 Tulsa, Oklahoma

Lease Name: Stevens Well No. 1

Location: C NW NW Sec. 32 Twp. 32 Rge. 29 (E) (W)

County Meade Total Depth 5814' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kelso was instructed to plug the well as follows:

13 3/8"-62' Cir. w/cement. 8 5/8"-1568' Cir. w/cement. 4 1/2"-5814' Cemented.

Top Perforations-5592'. Plug back to 5780'

Sand bottom well 5780' to 5500! 5 Sax. cement 5500' to 5440'.

Mud 5440' to 700' 35 Sax. 700' to 600'

Mud 600' to 50' Rock bridge 50' to 40'

15 Sax. cement 40' to 0

Very truly yours,

Stephen Scott
 Conservation Division Agent