

15-119-10216-0000

FORM - CP-2  
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
FEB 18 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

2-13-67

Mr. Luck of Thomas & Brewer has this

date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Box 1177, Liberal, Kansas

Lease Name: Angell Well No. 1

Location: NE NE Sec. 31 Twp. 32 Rge. 29 (E) (W)

County Meade Total Depth 5770' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8" to 1510' circulated w/ cement. 5 1/2" to 5740' cemented.

Top perforations 5625' Plug, Bottom W/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Eves  
Conservation Division Agent