

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 23 1965

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas & Brewer has this

date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Drawer 1177 Liberal, Kansas

Lease Name: Angell Well No. # A-1

Location: SW SW Sec. 29 Twp. 32 Rge. 29 (E/W)

County Meade Total Depth 5780' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8"-1480' Circulated w/cement. 4 1/2"-5770' Cemented. Top Perforations-  
5599'

Plug bottom w/20 Sax. cement top cement 5400' Mud 5400' to 700'

Spotted 35 Sax. cement 700' to 600' Mud 600' to 45'

Plug 15 Sax. cement 45' to 0

Very truly yours,

*[Signature]*  
 Conservation Division Agent